

*R*

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission  
Conservation Division  
800 Bitting Building  
Wichita, Kansas

FILE NO. \_\_\_\_\_

LOCATION NE-11W-21W

SEC. 4 TWP. 22 RGE. 13-W

Dry Hole \_\_\_\_\_ Abandoned Oil Well X Abandoned Gas Well \_\_\_\_\_

I have today completed supervision of plugging of:

Well No. 1 Lease Shadd

Operator Flourey & Williams Address #604 Brown Bldg - Wichita - Kans -

Field \_\_\_\_\_ County Stafford

Total Depth 3761 Feet.

(Describe briefly the manner in which the well was plugged)

Surface Pipe 8 1/2" - 321 ft. Circulated with cement  
5 1/2" casing set at 3754 ft. - Cemented with 250 sacks cement.  
Plugged back to 3740 ft. with chat - Dumped  
5 sacks of cement at 3740 ft. - Shot off & Pulled the 5 1/2" casing  
Filled with mud to 320 ft. Set Rock Bridge & 15 sacks  
of cement at 320 ft. - Mud to 30 ft. - Bridge &  
10 sacks of cement at the surface

RECEIVED  
STATE CORPORATION COMMISSION

OCT 24 1950 10-24-50

CONSERVATION DIVISION  
Wichita, Kansas

C. M. Stough  
District Conservation Agent

Date 10-21-50

PLUGGING  
FILE SEC. 4T 2V R 13W  
BOOK PAGE 37 LINE 44