

KANSAS

*28*  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
MAY 10 1971  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Operator's Full Name United States Hydrocarbon Co.

Complete Address Box 11027 Wichita, Ks

Lease Name Chase Well Service Well No. 2

Location 990' EWL & 810' SNL <sup>*SE NW NW*</sup> Sec. 4 Twp. 22S Rge. 13 (E) W

County Stafford Total Depth 3800

Abandoned Oil Well        Gas Well        Input Well        SWD Well        D & A X

Other well as hereafter indicated       

Plugging Contractor Garvey Drlg. Co.

Address Box 1164 Great Bend, Ks License No.       

Operation Completed: Hour 12:30 AM Day 8 Month 5 Year 1971

The above well was plugged as follows:

290 ft of 8 5/8 surface pipe cemented with 275 sacks. Pumped 40 sacks  
cement to 600 ft. Fill hole to 280 ft, pump 25 sacks cement. Mud to  
40 ft, 1/2 sack hulls, plug, 10 sacks cement to surface. 3 sacks  
cement in rat hole, 3 sacks cement in mouse hole.

Pumped by Globe Cementing Co. Great Bend, Ks

I hereby certify that the above well was plugged as herein stated.

Signed: *A. Russell B. Hunter*  
Well Plugging Supervisor

INVOICED

DATE 5/12/71  
INV. NO. 3662-U