

KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

RECEIVED
STATE CORPORATION COMMISSION

AUG 24 1965
8-24-65
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Kirby Petroleum Company
 Complete Address: 402 First National Bank Bldg., Wichita, Kansas
 Lease Name Kisner "B" Well No. # 1
 Location NE NE SE Sec. 3 Twp. 22 Rge. 13 (E) (W) W
 County Stafford Total Depth 3717'
 Abandoned Oil Well X Gas Well Input Well SWD Well D & A
 Other well as hereafter indicated:
 Plugging Contractor: Flint Engineering & Construction Company
 Address: Box 950, El Dorado, Kansas License No. 547
 Operation Completed: Hour 2:15 PM Day 19th Month August Year 1965

The Above well was plugged as follows:

270' of 8 5/8" surface pipe, cement circulated. 3713' of 5 1/2" long
string, cemented with 100 sacks. This is an open hole. Hole was sandéd
to 3700', and cemented with 5 sacks. 2800' of 5 1/2" long string was recovered
from the hole. Fluid was up in the hole. Bridge plug was pushed in fluid
to 250', rock bridge from 250' to 240'. 2 Sacks of Cal-Seal was mixed in
barrel, and put on plug at 240', through the dump bailer, and let set for
2 hours. Hole was bailed dry, and 25 sacks of cement was added to the plug.
Hole was filled with mud to 40', rock bridge from 40' to 30', and cemented
with 10 sacks to the base of the cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: Archie Elving
Well Plugging Supervisor

8-24-65
INV. NO. 1673-W