


STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 North Market, Insurance Bldg.
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Stafford County, Sec. 2 Twp. 22S Rge. (E) 13 (W)
Location as "NE/CNW/SW" or footage from lines c NW NE NW
Lease Owner Phillips Petroleum Co.
Lease Name Batman Well No. 4
Office Address Box 779 Great Bend, Kans.
Character of Well (completed as Oil, Gas or Dry Hole) Oil
Date well completed Oct. 29 19 53
Application for plugging filed July 30 19 59
Application for plugging approved August 3 19 59
Plugging commenced August 14 19 59
Plugging completed August 20 19 59
Reason for abandonment of well or producing formation Unprofitable to operate

If a producing well is abandoned, date of last production June 9 19 59
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well -
Producing formation Arbuckle Depth to top 3676 Bottom 3712 Total Depth of Well 3712 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Anhydrite		695		10 3/4"	401.80'	None
Toronto		3209		7"	3688.30'	2655'
Douglas		3223				
Br lime		3316				
LKC		3332	3557			
Viola		3588				
Simpson shale		3619				
Simpson sand		3619				
Arbuckle		3676				

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Dumped sand 3712 to 3452. Dumped 5 sx cement to 3426. Mudded hole to 250', set rock bridge to 240', 20 sx cement to 180', mudded hole to 40', set rock bridge to 30'.
Dumped 10 sx cement to base of cellar. Well plugged & abandoned 2 P.M. 8-20-59.

RECEIVED
STATE CORPORATION COMMISSION
AUG 24 1959
CONSERVATION DIVISION
Wichita, Kansas
8-24-59

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Knight Casing Pulling Company
Address Great Bend, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.
A. J. Willis (employee of owner) or (~~owner or operator~~) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) [Signature]
(Address) _____

SUBSCRIBED AND SWORN TO before me this 21st day of August, 19 59

My commission expires 11-18-61
[Signature] Notary Public.

PLUGGING
FILE SEC. 2 T. 22 R. 13W
BOOK PAGE 56 LINE 10

EXPLORATION RECORD

Lease Batman

Well 4

Formation Name	Top	Base	Remarks
Surface soil	0	224	
Sand, shale & shells	224	436	
Shale, anhydrite, red bed	436	979	
Anhydrite	979	1420	
Fort Riley	1420	1599	
Lime	1599	1993	
Lime & shale	1993	2263	
Shale	2263	2448	
Shell & shale	2448	2645	
Lime & shale	2645	3458	
Lime	3458	3525	
Lime & shale	3525	3559	
Lime, chert & shale	3559	3633	
Shale	3633	3668	
Lime	3668	3695	
Lime	3695	3712 *	Well deepened
			Tops:
			Anhydrite 695
			Heebner 3188
			Toronto 3209
			Douglas 3223
			Br Lime 3316
			LKC 3332
			Base KC 3557
			Viola 3588
			Simp. shale 3619
			Simp. sand 3649
			Arb. 3676

PLUGGING
 FILE SEC 2122R13a
 BOOK PAGE 56 LINE 10

RECEIVED
 STATE CORPORATE COMMISSION
 AUG 24 1953
 CONSERVATION DIVISION
 Wichita, Kansas