

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
130 S. Market, Room 2078  
Wichita, KS 67202

K.A.R.-02-3-117  
15-185-11198-0000

API NUMBER 7-14-47

LEASE NAME Batman

WELL NUMBER 1

330 Ft. from S Section Line

1650 Ft. from E Section Line

SEC. 2 TWP. 22 RGE. 13 XXX (X)

COUNTY Stafford

Date Well Completed JULY 11, 1917

Plugging Commenced 8-3-98

Plugging Completed 8-5-98

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR Poorboy Corporation

ADDRESS Rt 2 - Box 109 A Ellinwood, Ks. 67526

PHONE (316) 793-7223 OPERATORS LICENSE NO. 6458

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 8-13-98 (date)

by David P. Williams (KCC District Agent's Name)

Is ACO-1 filled?    If not, is well log attached?   

Producing Formation ARB. KC. Depth to Top 3388' Bottom 3730' T.D. 3730'

Show depth and thickness of all water, oil and gas formations.

8-27-98

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				10 3/4"	419'	
				7"	3695'	2418'

KANSAS RECEIVED

Describe in detail the manner in which the well was plugged, indicating where the plug was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet. Sanded to 3330'. Bailed 7 sks cement. Shot at 2418'. Pulled to 700'. Pumped 15 gel/50 sks cement. Pulled to 430'. pumped 70 sks cement. Pulled to 31'. Pumped 15 sks cement. pulled the rest of the pipe. Hole stayed full. Plug fell to 412'. Ran to 370'. Pumped 10 gel. Pulled to 150'. Circulated cement to surface with 90 sks cement. Hole stayed full.

Name of Plugging Contractor Quality Well Service, Inc. License No. 31925

Address 249 Beth Drive Sterling, Ks. 67579-9048

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Poorboy Corporation

STATE OF Kansas COUNTY OF BARTON, ss.

LOREN D. HADDON (Employee of Operator or Operator)


above-described well, being first duly sworn on oath, says: That I have knowledge of the facts and statements, and matters herein contained and the log of the above-described well as filed and the same are true and correct, so help me God.

(Signature) Loren D. Haddon

(Address) RR2 ELLINWOOD, KANSAS 67526

DESCRIBED AND SWORN TO before me this 25 day of August, 1998

Ledje O Guesner  
Notary Public



My Commission Expires: 3-9-01

USE ONLY ONE SIDE OF EACH FORM