


STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Stafford County, Sec. 2 Twp. 22 Rge. (E) 13 (W)
Location as "NE/CNW/SW" or footage from lines SW - SW - SE
Lease Owner Great Bend Pipe & Supply
Lease Name Batman Well No. 7
Office Address Great Bend, Kansas
Character of Well (completed as Oil, Gas or Dry Hole)
Date well completed 19
Application for plugging filed 19
Application for plugging approved 19
Plugging commenced 2-7-59 19
Plugging completed 2-13-59 19
Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Frank Broadfoot
Producing formation Depth to top Bottom Total Depth of Well Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	320	None
				5 1/2	3733	3284.48

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled with sand from 3752' to 3725' - dumped 5 sks cement - bailed oil out of hole - mudded to 250' - set 10' rock bridge - dumped 15 sks cement - mudded to 40' - set rock bridge - dumped 10 sks cement to base of cellar.

RECEIVED
STATE CORPORATION COMMISSION

FEB 19 1959 2-19-59

VISION

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor R & D Casing Pulling Company License # 236
Address Box 569 Ellinwood, Kansas

STATE OF Kansas COUNTY OF Barton ss.
Notker Melzer (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Notker Melzer
Box 191, Great Bend, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 18th day of February, 1959

Notker Melzer
Notary Public.

My commission expires 3/30/61

PLUGGING
FILE SEC. 2 T. 22 R. 13W
BOOK PAGE 14 LINE 7


COPY

Company- PLAINS EXPLORATION CO.
 Farm- Batman No. 7

SEC. 2 T. 22 R. 13W
 SW SW SE

Total Depth. 3752'
 Comm. 11-24-57 Comp. 12-4-57
 Shot or Treated.
 Contractor. Sterling Drlg. Co.
 Issued. 6-21-58

County Stafford
 KANSAS



Elevation. 1880' KB

Production. 20 BOPD

CASING:

8 5/8" 320' cem w/320 sx.
 5 1/2" 3733' cem w/60 sx.

Figures Indicate Bottom of Formations.

sand	180
shale, shells, red bed	320
shale & red bed	720
Anhydrite	850
shale & lime	2900
lime	3050
lime & shale	3150
lime	3215
lime & shale	3315
lime	3585
lime & shale	3665
lime	3675
shale & lime	3735
lime	3752
Total Depth	

TOPS:

Heebner	3217
Toronto	3239
Brown Limestone	3348
Lans-Kansas City Groups	
Undifferentiated	3365
Base Kansas City	3593
Basal Pennsylvanian Conglomerate	3620
Viola	3632
Simpson	3673
Weathered Arbuckle	3726
Arbuckle	3733

DST #1 3373-3401, tool open 30 mins, weak blow for 10 mins, flushed tool once. rec. 15' of mud. 30 min shut in bottom hole pressure 390#.

DST #2 3634-3675 tool op 45 mins, weak blow for 7 mins, flushed tool twice. Rec. 70' of mud w/occasional spot of oil. 30 min SIBHP 125#, IFP 45#, FFP 88#.

RECEIVED
 STATE CORPORATION COMMISSION
 FEB 5 1959
 CONSERVATION DIVISION
 Kansas

PLUGGING
 FILE SEC. 2 T. 22 R. 13W
 BOOK PAGE 14 LINE 19