

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Stafford County. Sec. 2 Twp. 22 Rge. 13 (E) (W)

Location as "NE/CNW%SW%" or footage from lines _____

Lease Owner Anschutz Drilling Company, Inc.

Lease Name Bunselmeyer Well No. 5

Office Address _____

Character of Well (completed as Oil, Gas or Dry Hole) _____

Date well completed 1-12-54 19__

Application for plugging filed 8- 5-63 19__

Application for plugging approved 8- 6-63 19__


Plugging commenced August. 7. 1963 19__

Plugging completed August. 12. 1963 19__

Reason for abandonment of well or producing formation Well reached economic limit.

If a producing well is abandoned, date of last production 7-2-63 19__

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes



Locate well correctly on above
Section Plat

Name of Conservation Agent who supervised plugging of this well Archie V. Elving Pratt, Kansas

Producing formation Arbuckle Depth to top 3662 Bottom - Total Depth of Well 3672 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Arbuckle	Oil	3662	3672 (TD)	8-5/8	278	0
				5-1/2	3663	3055

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Plugged, back with sand to 3650-feet, Dumped 5- sacks cement.
Set a rock-bridge at 270-feet, Dumped 5- sacks cement.
Bailed hole down and filled hole with Ready Mix Cement.

RECEIVED
STATE CORPORATION COMMISSION

AUG 23 1963

8-23-63

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor LYNCH CASING PULLING COMPANY NO. 457

Address R.R.T. 4 GREAT BEND, KANSAS

STATE OF Colorado, COUNTY OF Denver, ss. Anschutz Oil Co., Inc. (employee or owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) John D. Hefey
380 Denver Hilton Office Building, Denver 2,

(Address) Colorado

SUBSCRIBED AND SWORN TO before me this 21st day of August, 19 63

My commission expires October 29, 1963

Shirley Stearn
Shirley Stearn Notary Public.

DRILLER'S LOG

Anschutz Drilling Company
 #5 Bunselmeyer
 SW SW NE 2-22S-13W
 Stafford County, Kansas

FROM	TO	
0	210	Sand
210	283	Red Bed
283	715	Shale & Shells
715	750	Anhydrite
750	1355	Shale & Shells
1355	1590	Shale & Lime
1590	1875	Lime
1875	2110	Lime & Shale
2110	2380	Shale & Lime
2380	2675	Shale
2675	2910	Shale & Lime
2910	3193	Lime
3193	3275	Shale & Lime
3275	3545	Lime
3545	3620	Lime & Chert
3620	3665	Lime
	3665	ROTARY TOTAL DEPTH

COMMENCED: 12-21-53
 COMPLETED: 1-3-54

CASING RECORD

Set 8-5/8" surface casing at
 278' with 320 sacks cement

RECEIVED
 STATE CORPORATION COMMISSION

AUG 23 1963

CONSERVATION DIVISION
 Wichita, Kansas

STATE OF KANSAS)
) SS
 COUNTY OF SEDGWICK)

I hereby affirm that the above and foregoing is a true and correct copy of the log of the #5 Bunselmeyer SW SW NE of Section 2-22S-13W, Stafford County, Kansas.

ANSCHUTZ DRILLING CO., INC.

By E. G. Koelling
 E. G. Koelling

Subscribed and sworn to before me this 11th day of March, 1954.

Helmut J. Sawyer
 Notary Public

My Commission Expires: November 21, 1956