


STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
809 Bittig Building
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Stafford County. Sec. 2 Twp. 22 Rge. 13W (X) (W)
Location as "NE/CNWxSWx" or footage from lines SE SW NE
Lease Owner Fred B. Anschutz
Lease Name Bunselmeyer Well No. 4
Office Address 1019 Central Bldg, Wichita 2, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Oil
Date well completed 6-26-1956
Application for plugging filed 5-17-1956
Application for plugging approved 5-18-1956
Plugging commenced 6-1-1956
Plugging completed 6-7-1956
Reason for abandonment of well or producing formation Depleted

If a producing well is abandoned, date of last production 5-1-1956
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well R. M. Brundage
Producing formation Arbuckle Depth to top 3685 Bottom 3706 Total Depth of Well 3706 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Arbuckle	oil	3685	3706	8-5/8"OD 5-1/2"OD		None 2795

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Sand 3691 to 3670
5 sax cement 3670' to 3645'
Mud 3645 - 240
rock bridge 240 - 230
20 sax cement 230 - 170
mud 170 - 35
10 sax cement to top.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor R & S Pulling Co.
Address Ellinwood, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss. Agent
John W. Ritchey (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) *John W. Ritchey*
1019 Central Bldg., Wichita 2, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 20th day of June, 1956

My commission expires Jan. 31, 1957
Seward S. Greider Notary Public.

6-21-56

CONSERVATION DIVISION
Wichita, Kansas

PLUGGING
FILE SEC 2 T 22 R 13W
BOOK PAGE 62 LINE 20

15.185.10887.0000


WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY
503 East Murdock, Wichita, Kansas

Company- ANSCHUTZ DRILLING CO.
Farm- Bunselmeyer No. 4

SEC. 2 T. 22 R. 13W
SE SW NE

Total Depth. 3706
Comm. 5-20-53 Comp. 5-31-53
Shot or Treated.
Contractor.
Issued. 8-22-53

County Stafford
KANSAS



CASING:
8 5/8 @ 247' w/ 225 sx cem.
5 1/2 @ 3686' w/ 75 sx cem.

Elevation. 1883 RB

Production. 31 BO, 18% water

Figures Indicate Bottom of Formations.

sand	227
shale	250
shale & red rock	720
anhydrite	740
shale & red rock	760
shale & shells	1605
lime	1735
lime & shale	3395
lime	3512
lime & shale	3581
conglomerate & chert	3636
lime & shale	3684
Arbuckle	3706
Total Depth	

TOPS: (RB)	
Anhydrite	720
Heebner	3194
Iatan	3324
Lansing KC	3342
Base KC	3566
Cherty conglomerate	3584
Viola residual chert	3600
Simpson	3630
Arbuckle	3684

No DST's

STATE OF KANSAS
WELL LOG BUREAU
WICHITA, KANSAS

PLUGGING
FILE SEC. 2 T. 22 R. 13W
BOOK PAGE 62 LINE 20