


Give All Information Completely
Make Required Affidavits
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittig Building
Wichita, Kansas

WELL PLUGGING RECORD



Locate well correctly on above Section Plat

Stafford County, Sec. 2 Twp. 22 Rge. (E) 13 (W)
Location as "NE/CNW/SW" or footage from lines NW NE NE
Lease Owner Fred B. Anschutz
Lease Name Bunselmeyer Well No. 2
Office Address 1019 Central Building, Wichita 2, Kansas.
Character of Well (completed as Oil, Gas or Dry Hole) oil
Date well completed 1-18-19 53
Application for plugging filed 6-11-19 56
Application for plugging approved 6-11-19 56
Plugging commenced 6-28 19 56
Plugging completed 7-6 19 56
Reason for abandonment of well or producing formation Depleted

If a producing well is abandoned, date of last production 7-26-19 56
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well R. M. Bruandage
Producing formation Arbuckle Depth to top 3667 Bottom _____ Total Depth of Well 3694 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Arbuckle	oil	3667	3694	5-7/8"	3693'	2847'
				8-5/8"	280'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

3683' to 3650' sand
3650' to 3625' 5 sacks cement
3625' to 230' mudded
230' to 220' rock bridge
220' to 160' 20 sacks cement
160' to 35' mud
35 to cellar 10 sacks cement

1-17
STATE CORPORATION COMMISSION
AUG 10 1956
CONSERVATION DIVISION

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor R & S Pipe Pulling Co. 8-10-56
Address Ellinwood, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss. Agent
John W. Ritchey (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) John W. Ritchey
July 23, 1956, 1019 Central Bldg., Wichita, Ks.
(Address)

SUBSCRIBED AND SWORN to before me this 23rd day of July, 19 56

Marie C. Murphy
Notary Public.

My commission expires April 23, 1958

PLUGGING
FILE SEC 2 T 22 R 13w
BOOK PAGE 69 LINE 34

DRILLER'S LOG

Anschutz Drilling Co., Inc.
 #2 Bunselmeyer
 NW NE NE Sec. 2-225-13W
 Stafford County, Kansas

TO	FROM	DESCRIPTION
0	230	Sand
230	265	Shale and Shells
265	700	Red Bed & Shale
700	730	Anhydrite
730	940	Shale
940	1230	Shale & Shells
1230	1470	Salt
1470	1615	Shale & Lime
1615	1740	Lime & Shale
1740	1905	Lime
1905	2050	Lime & Shale
2050	2175	Lime & Shale
2175	2265	Shale & Lime
2265	2440	Shale & Lime
2440	2630	Shale
2630	2850	Shale & Lime
2850	2950	Lime
2950	3050	Lime & Shale
3050	3216	Lime
3216	3295	Shale & Shells
3295	3365	Lime & Shale
3365	3552	Lime
3552	3620	Lime & Chert
3620	3694	Lime
3694		ROTARY TOTAL DEPTH

Commenced: 1-18-53

Completed: Feb. 2, 1953

Set 2:01" 8 5/8" surface casing with 295 sacks of cement and 25 Calcium Chloride.

Set 5 1/2" casing at 3093 with 100 sacks of cement.

STATE OF KANSAS)
) ss
 CITY AND COUNTY OF DENVER)

I hereby affirm that the above and foregoing is a true and correct copy of the log of the #2 Bunselmeyer located in the NW NE NE Section 2-225-13W, Stafford County, Kansas.

ANSCHUTZ DRILLING CO., INC.

By:

L. E. Walker
 L. E. Walker

Subscribed and sworn to before me this 20th day of July, 1956.

My Commission Expires: October 4, 1959

Notary Public

RECEIVED
 STATE CORPORATION COMMISSION
 AUG 10 1956
 CONSERVATION DIVISION
 Wichita, Kansas

PLUGGING
 FILE SEC 2 T 22 R 13W
 BOOK PAGE 69 LINE 34