

STATE OF KANSAS
STATE CORPORATION COMMISSION


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

WELL PLUGGING RECORD

v Stafford County. Sec. 2 Twp. 22 Rge. 13 (E) (W)

Location as "NE/CNW/SW" or footage from lines NW NW SE
Lease Owner Specter Pipe & Supply, Inc.
Lease Name Batman Well No. 5
Office Address Russell, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) oil
Date well completed 6-18-53 19
Application for plugging filed March 29, 1968 19
Application for plugging approved April 1, 1968 19
Plugging commenced 5/5/ 19 68
Plugging completed 5/17 19 68
Reason for abandonment of well or producing formation Dry

NORTH



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was com-
menced? Yes

Name of Conservation Agent who supervised plugging of this well Ralph Warren
Producing formation Arbuckle Depth to top 3665 Bottom 3666 Total Depth of Well 3721 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8" OD	265 ft.	none
				5 1/2" OD	3666	1454 feet

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Plugged back to 3300' with sand. 5 sacks cement.
set 10' rock bridge at 250', 25 sacks cement.
Mudded to 40'. Set 10' rock bridge.
Topped with 10 sacks cement.

RECEIVED
STATE CORPORATION COMMISSION
MAY 29 1968
CONSERVATION DIVISION
Wichita, Kansas

5-29-68

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Lynch Casing Pulling
Address Rt 4, Great Bend, Kansas

STATE OF Kansas COUNTY OF Russell, ss.
Specter Pipe & Supply, Inc. (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Martin Specter
Russell, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 25th day of May, 1968

Nilsen M. Lindahl
Notary Public.

My commission expires May 21, 1971

COPY


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- PLAINS EXPLORATION COMPANY
Farm- Batman No. 5

SEC. 2 T. 22 R. 13W
NW NW SE

Total Depth. 3670
Comm. 6-8-53 Comp. 6-18-53
Shot or Treated.
Contractor. Anschutz Drlg. Co.
Issued. 11-7-53

County Stafford
KANSAS



Elevation. 1882 DF

Production. Pumped 50 bbls. oil
& 10 wtr.

CASING:

8 5/8" 265' cem. w/225 sx
5 1/2" 3666' cem. w/ 100 sx

Figures indicate Bottom of Formations.

sand	235
redrock	265
redbed & shells	710
Anhydrite	740
shale & shells	1240
salt & shale	1420
shale & shells	1540
lime & shale	1630
lime	1755
sandy lime & shale	1890
lime & shale	2035
lime	2185
shale & lime	2410
shale	2605
shale & lime	2985
lime	3185
lime & shale	3350
lime	3670
Total depth	

Tops:	
Heebner	3190
Toronto	3212
Brown lime	3319
Lansing	3337
Base Kansas City	3558
Conglomerate	3575
Viola	3587
Simpson	3621
Arbuckle	3665

Remarks:

Drill Stem Test No. 1

HONCO TOOL

Depth: 3410-35, Tool open 1 hr -
shut in 25 minutes

Blow: Good, throughout test

Recovery: 160' salt water

Bottom Hole Pressure: 1060#.

RECEIVED
STATE CORPORATION COMMISSION
APR 1 1968
CONSERVATION DIVISION
Wichita, Kansas