


STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Bitting Building  
Wichita, Kansas

Stafford County. Sec. 2 Twp. 22 Rge. 13 (X) W (W)

Location as "NE/CNW/SW" or footage from lines SE NW NE  
Lease Owner Fred B. Anschutz  
Lease Name Bunselmeyer Well No. 7  
Office Address 706 Union Nat'l Bank Bldg., Wichita, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed Aug. 26 19 54  
Application for plugging filed Aug. 26 19 54  
Application for plugging approved Aug. 26 19 54  
Plugging commenced Aug. 26 19 54  
Plugging completed Aug. 26 19 54  
Reason for abandonment of well or producing formation Dry



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well M. A. Rives  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well \_\_\_\_\_ Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	254'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Hole filled with crushed rock to 250'  
1st plug set @ 250' with 1/2 sack hulls & 20 sacks cement  
2nd plug set @ 40' with 1/2 sack hulls & 2 sacks cement

9-3-54  
STATE CORPORATION COMMISSION  
WICHITA, KANSAS

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Anschutz Drilling Co., Inc.  
Address 709 Union Nat'l Bank Bldg., Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.  
E. G. Koelling (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God

(Signature) E. G. Koelling  
709 Union Nat'l Bank Bldg., Wichita, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 1st day of September 19 54

Dilma V. Chapman  
Notary Public.

My commission expires May 24, 1956

24-7368-S 3-53-20M

PLUGGING  
FILE SEC 2 T 22 R 13N  
BOOK PAGE 60 LINE 15

DRILLER'S LOG

Fred B. Anschutz  
 Bunselmeyer #7  
 SE NW NE 2-22-13  
 Stafford County, Kansas

To	FROM	
0	71	Sand & Clay
71	220	Sand
220	257	Shells & Red Rock
257	800	Red Rock & Shells
800	1215	Shale & Shells
1215	1485	Shale, Salt & Shells
1485	1620	Lime & Shale
1620	1910	Lime
1910	2015	Lime & Shale
2015	2245	Shale & Lime
2245	2360	Lime & Shale
2360	2710	Shale & Shells
2710	2830	Shale & Lime
2830	3366	Lime & Shale
3366	3585	Lime
3585	3735	Conglomerate
	3735	ROTARY TOTAL DEPTH

COMMENCED: 8-16-54  
 COMPLETED: 8-27-54

CASING RECORD:

Set 254' of 8 5/8" surface casing with 225 sx. cement.

D & A

STATE OF KANSAS )  
 ) SS  
 COUNTY OF SEDGWICK )

I hereby affirm that the above and foregoing is a true and correct copy of the log of the Bunselmeyer #7 located SE NW NE of Section 2-22-13, Stafford County, Kansas.


ANSCHUTZ DRILLING CO., INC.

BY: *E. G. Koelling*  
 E. G. Koelling

Subscribed and sworn to before me this 2nd day of September, 1954.

*Charlene Barbour*  
 Notary Public

My Commission Expires: July 28, 1958.



**PLUGGING**  
 FILE SEC 2 T 22 R 13N  
 BOOK PAGE 100 LINE 15

RECEIVED  
 STATE OPERATIONS COMMISSION  
 SEP 23 1954  
 CONSERVATION DIVISION  
 Wichita, Kansas