


STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

15-009-01379-0000
WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Barton County. Sec. 3 Twp. 16S Rge. 12 (E) W (W)

Location as "NE/CNW/SW" or footage from lines NE NW SE

Lease Owner Coppinger Drilling, Inc.

Lease Name Polzin Well No. 1

Office Address 320 Union National Bank Bldg., Wichita, Ks.

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed 10-25 19 53

Application for plugging filed 10-25 19 53

Application for plugging approved 10-25 19 53

Plugging commenced 10-25 19 53

Plugging completed 10-25 19 53

Reason for abandonment of well or producing formation Non-Productive

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well C. D. Stougie

Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3364 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8	181	Circulated to surface
<p>RECEIVED STATE CORPORATION COMMISSION OCT 30 1953 10-30-53 CONSERVATION DIVISION</p>						

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Mud to 181'. Wood plug and 1/3 sack hulls at 181'. 20 sacks mixed cement on top of plug. Mud to 40'. Wood plug and 1/3 sack hulls at 40'. 10 sacks mixed cement to surface.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Mallonee Drilling Company, Inc.
Address 812 Central Bldg., Wichita 2, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.
F. W. Mallonee, agent of operator (employee-of-owner) or (owner-or-operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) F. W. Mallonee
812 Central Bldg., Wichita, Ks.
(Address)

SUBSCRIBED AND SWORN TO before me this 26th day of October, 19 53

My commission expires March 7, 1957 R. E. Mallonee Notary Public.

PLUGGING
FILE SEC 3 T 16 R 12W
BOOK PAGE 138 LINE 44

DRILLER'S LOG
 NO. 1 POLZIN
 NE NW SE SEC. 3-16-12W
 BARTON COUNTY, KANSAS

OPERATOR: Coppinger Drilling, Inc.
 CONTRACTOR: Mallonee Drilling Company, Inc.
 COMMENCED: 10-15-53
 COMPLETED: 10-25-53

Elev.: 1898 K. B.
 D & A

FROM	TO	DESCRIPTION	REMARKS
0	30	Surface soil, sand & gravel	
30	45	Gravel	
45	90	Shale	
90	110	Sand and shale	
110	181	Shale	Set 183' 8-5/8 surface casing at 181' with 100 sks & 1 c.c.
181	215	Shale	
215	400	Sand & shale	
400	500	Sand and pyrites	
500	690	Red bed & shale	
690	1065	Anhydrite	
1065	1455	Shale, shells & salt	
1455	1550	Shale & lime shells	
1550	1950	Lime and shale	
1950	2030	Lime	
2030	2165	Lime & shale	
2165	2310	Shale & shells	
2310	2730	Shale & Lime	
2730	3000	Lime	
3000	3065	Lime & shale	
3065	3364	Lime	
	3364	Total Depth of Hole	

TOPS:			
Anhydrite	1025	+	868
Heebner	2967	-	1069
Toronto	2985	-	1087
Lansing	3073	-	1175
Base K. C.	3275	-	1377
Sand	3350	-	1452
Arbuckle	3359	-	1461
Total Depth	3364	-	1466

I certify that to the best of my knowledge and belief the above is a true and accurate Driller's Log record of the above-captioned well.

J.W. Mallonee

Subscribed and sworn to before me this 26th day of October, 1953.

R.E. Mallonee

Notary Public
 RECEIVED
 STATE CORPORATION COMMISSION

My commission expires: 3-7-57

PLUGGING
 FILE SEC 3-16-R/2W
 BOOK PAGE 138 LINE 44

OCT 30 1953
 CONSERVATION DIVISION
 Wichita, Kansas