

Barton County, Sec. 3 Twp. 16 Rge. 12 (E) W (W)

Location as "NE/CNW%SW%" or footage from lines C E/2 NE/4 SW/4

Lease Owner Morris Sitrin, Inc.

Lease Name Polzin Well No. One

Office Address P. O. Box 1160, Tulsa, Oklahoma

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed August 7 19 63

Application for plugging filed August 7 19 63

Application for plugging approved August 7 19 63


Plugging commenced August 7 19 63

Plugging completed August 7 19 63

Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production _____ 19 _____

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well Gilbert Leiker

Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3,375 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

| FORMATION | CONTENT | FROM | TO | SIZE | PUT IN | PULLED OUT |
|-----------|---------|------|----|--------|--------|----------------|
| | | | | 8 5/8" | 265' | Cmtd w/175 sax |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Fill w/heavy mud to 265'
Set bridging plug @ 265' w/ 1/4 sax hulls on plug
Dump 20 sax cement on plug thru 4 1/2" drill pipe
Fill w/heavy mud to 40'
Set bridging plug @ 40' w/ 1/2 sax hulls on plug
Dump 10 sax cement on plug to cellar

RECEIVED
 STATE CORPORATION COMMISSION

OCT 8 1963

10-8-63

CONSERVATION DIVISION
 Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Shields Drilling Company, Inc.

Address Shields Bldg., Russell, Kansas

STATE OF Oklahoma, COUNTY OF Tulsa, ss.

Larry Sitrin (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Larry Sitrin

P. O. Box 1160 Tulsa, Oklahoma

(Address)

SUBSCRIBED AND SWORN to before me this 2nd day of October, 1963

Meredith E. Norris

Notary Public.

My commission expires May 7, 1966






Shields

Russell, Kansas

WELL LOG

Operator: Morris Sitrin, Inc.
 Well: Polzin #1
 Commenced: July 30, 1963
 Completed: August 7, 1963
 Contractor: Shields Drilling Company, Inc.

Well Description C E/2 NE/4 SW/4
 Sec. 3-16S-12W
 Barton County, Kansas



| CASING RECORD | | |
|---------------|------|----------------|
| Size | Run | Pulled |
| 8 5/8" | 265' | Cmtd w/175 sax |

Elevation: 1,885'
 Treatment:
 Production: D & A
 Tops:

..... Figures Indicate Bottom of Formations

| | |
|---------------------------|------------|
| Post rock, shale & shells | 265' |
| Shale, shells & sand | 470' |
| Hard sand | 490' |
| Redbed | 715' |
| Shale & redbed | 798' |
| Anhydrite | 835' |
| Shale, shells & redbed | 1,100' |
| Shale | 1,500' |
| Lime & shale | 2,765' |
| Lime | 3,375' RTD |

NOTES

DST #1 3,346'-75' Tool open 1 hr. w/good blow thruout.
 Recovered 350' muddy water
 IFP-33#, FFP-199#, FBHP-803#/30 min.

RECEIVED
 STATE CORPORATION COMMISSION

OCT 3 1963

CONSERVATION DIVISION
 Wichita, Kansas