


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD 15-009 - 21361

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Barton County. Sec. 3 Twp. 16 Rge. #12W/W
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines C NE SE

Lease Owner S-L Production Co. Inc.
Lease Name Schauf Well No. B-I
Office Address P.O.Box 191 McPherson, Kansas 67460
Character of Well (Completed as Oil, Gas or Dry Hole) Dry



Locate well correctly on above Section Plot

Date Well completed 4-27 1978
Application for plugging filed 6-9 1978
Application for plugging approved 6-10 1978
Plugging commenced 6-12 1978
Plugging completed 6-16 1978
Reason for abandonment of well or producing formation _____

If a producing well is abandoned, date of last production 19____

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Dwain Rankin
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3333'
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				<u>5 1/2"</u>		<u>2,742'</u>

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set. Pushed plug to 3075'. Sanded hole to 3050'. Dumped 5 sx of cement. Pumped 5 sx Halls; 25 sx Mud; 100 sx Cement. Max Pump Pressure 1000 lbs. Closed-in pump pressure 500 lbs. with Sun Cementing Co.

RECEIVED
STATE CORPORATION COMMISSION
JUN 19 1978

CONSERVATION DIVISION
Wichita, Kansas 06-19-78

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Art Shank Casing Tapping Inc.

STATE OF Kansas COUNTY OF Leawards, ss. Art Shank (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Art Shank
2809 King-Hutchinson, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 16th day of June, 1978

My commission expires April 18, 1982
Judy Shank
Notary Public.

DRILLER'S WELL LOG

DATE COMMENCED: 4-21-78
DATE COMPLETED: 4-27-78

S-L Production Co., Inc.
Schauf B-1
Approx. C NE SE, Sec. 3-16-12W,
Barton County, Kansas

ELEVATION: 1893' K.B.
1888' G. L.

FORMATION DATA

0- 800'	Sand and Red Bed
800- 824'	Anhydrite
824-2678'	Lime
2678-2964'	Lime
2964-2969'	Shale
2969-2978'	Lime
2978-3000'	Lime
3000-3053'	Shale
3053-3065'	Lime and Shale
3065-3260'	Lime
3260-3330'	Lime and Shale
3330-3333'	Dolomite
3333'	T. D.

Anhydrite	800
Topeka	2678
Heebner	2964
Toronto	2978
Douglas	3000
Brown Lime	3053
Lansing	3065
Base Kansas City	3260
Arbuckle	3330
T. D.	3333

Plug set @ 3286'
Perforated 3248-3252'

RECEIVED
STATE CORPORATION COMMISSION
JUN 12 1978
CONSERVATION DIVISION
Wichita, Kansas

SURFACE PIPE:

Ran 7 Jts. Used 8 5/8" 28# Casing
Tally 246'. Set @ 252' w/160 sks
Common. 2% Gel, 3% c.c. By Sun
Cementing. P.D. @ 9:45 p.m. Ceme
did circulate.

PRODUCTION PIPE:


Ran 100 Jts. used 14# - 5/2" Casir
Tally 3329'. Set @ 3331' w/60 sl
Salt Saturated, 2% Gel Common. 1
Sun Cementing. P.D. @ 11:00 p.m.

A F F I D A V I T

STATE OF KANSAS }
COUNTY OF BARTON } ss.

DALE L. SMITH, of lawful age, does swear and state that the fact
and statements herein contained are true and correct to the best of his
knowledge.

Dale Smith



Subscribed and sworn to before me this 28th day of April 1978.

Wanda Nichols
Notary Public

My commission Expires: 1-28-1980