

STATE OF KANSAS
TATE CORPORATION COMMISSION
30 S. Market, Room 2070
Wichita, KS 67202

WELL PLUGGING RECORD
K.A.R.-02-3-117

API NUMBER 15-185-21,460-00-00

LEASE NAME Fisher "A"

WELL NUMBER 1

 Ft. from S Section Line

 Ft. from E Section Line

SEC. 2 TWP. 22 RGE. 13W (E) or (W)

COUNTY Stafford

Date Well Completed

Plugging Commenced 3-12-01

Plugging Completed 3-13-01

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR GLOBE OPERATING, INC.

ADDRESS P.O. Box 12 Great Bend, Kansas 67530

PHONE (316) 792-7607 OPERATORS LICENSE NO. 6170

Character of Well Oil

(Oil, Gas, D&A, SHD, Input, Water Supply Well)

The plugging proposal was approved on (date)

by Richard Lacey (KCC District Agent's Name).

Is ACO-1 filed? If not, is well log attached?

Producing Formation Depth to Top Bottom T.D. 3800'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

3-20-01 RECEIVED
CASING RECORD STATE CORPORATION COMMISSION

Formation	Content	From	To	Size	Put In	Pulled out
				8-5/8"	270	None
				5-1/2"	3798'	2600'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugging material was used, state the character of same and depth placed, from feet to feet each string. Plugged off bottom with sand to 3745' and 5 sks. cement. Shot pipe @2600' and 2410', pulled up to 734', pumped 10 sks. gel, 50 sks. cement, pulled to 300', pumped 50 sks. cement, pulled to 40', pumped 10 sks. cement. 60/40 pos. 6% gel. Plugging Complete.

Name of Plugging Contractor Mike's Testing & Salvage, Inc. License No. 31529

Address P.O. Box 467 Chase, Kansas 67524

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Globe Operating, Inc.

STATE OF Kansas COUNTY OF Rice, ss.

Mike Kelso (Employee of Operator) or (Operator) above-described well, being first duly sworn on oath, says: That I have knowledge of the facts and matters herein contained and the log of the above-described well as filed in the same are true and correct, so help me God.


(Signature) Mike Kelso

(Address) P. O. Box 467 Chase, KS 67524

SUBSCRIBED AND SWORN TO before me this 16th day of March, 2001

Irene Herzberg
Notary Public

My Commission Expires:



Form CP
Revised 05-