

KANSAS



STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
DEC 31 1970
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Spector Pipe & Supply Inc.

Complete Address Box 169 Russell, Ks

Lease Name Moon Well No. 3

Location SE/SE/NW Sec. 15 Twp. 22 Rge. 13 (E) (W) W

County Stafford Total Depth 3810

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated _____

Plugging Contractor Lynch Casing Pulling Co.

Address Rt. 4 Great Bend, Ks License No. 457

Operation Completed: Hour 4:00 PM Day 29 Month 12 Year 1970

The above well was plugged as follows:

304 ft of 8 5/8 surface pipe cemented with 275 sacks. 3791 ft of
5 1/2 long string cemented with 100 sacks. Open hole. Sand back to
3500 ft, 5 sacks cement with bailer. Pulled 2740 ft of 5 1/2. Pumped
2 sacks hulls, 15 sacks gel mud & 100 sacks cement to surface.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 12/31/70

INV. NO. 3140-W

Signed: [Signature]
Well Plugging Supervisor