

KANSAS

4

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

15-009-15117-0000

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

RECEIVED
STATE CORPORATION COMMISSION
JUL 3 1972
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Joe Brougher Oil Company

Complete Address 5513 Apache, Great Bend, Kansas 67530

Lease Name Harzman Well No. # 8

Location W/2 SW SW Sec. 33 Twp. 16 Rge. 11 (E) (W)W

County Barton Total Depth 3356

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Russ Casing Pulling, Inc.

Address Box 1082, Great Bend, Kansas License No. # 623

67530

Operation Completed: Hour 9:45 A.M. Day 30 Month 6 Year 1972

The above well was plugged as follows:

8 5/8" 376' Cwc. Perf. 3310'.

Sanded hole back to 3275' & dumped 5 sax cement with dump bailer. Pulled pipe.

Squeezed well with 3 sax hulls. 20 sax mud, & 100 sax cement with Halliburton

Cementing Company's pump truck, cementing from 340' to base of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: Don Stewart
Well Plugging Supervisor

INVOICED

DATE 7-5-72

INV. NO. 5980-102