

KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT REPORT

STATE CORPORATION COMMISSION
RECEIVED
OCT 07 1982
CONSERVATION DIVISION
Wichita, Kansas
FORM CP-3
Rev. 1-8-82

API Number 15-009-D3192-000

200 Colorado Derby Building
Wichita, KS 67202

Operator's Full Name Santa Fe Pipe & Supply, Inc.

Complete Address P.O. Box 562, Great Bend, Ks. 67530

Lease Name Hargman Well No. #2

Location SW SW SE Sec. 33 Twp. 16 Rge. 11 (East) (West)

County Barton Total Depth 3336'

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated _____

Plugging Contractor Rockhold Engineering, Inc.

Address P.O. Box 698, Great Bend, Ks. 67530 License No. _____

Operation Completed: Hour: 2:00 PM Day: 1 Month: 10 Year: 1982

Plugging Operations attended by Agent?: All Part None

The above well was plugged as follows:

9 5/8" - 196' SP casing w/ 125 sacks cement. 5 1/2" set at 3332' w/ 100 sacks cement
4' of open hole. Ordered 215 sacks 50 permix - 47% Sol. - 3% Cal. Cl., 5 sacks hulls,
15 sacks Sol. to 5 1/2" plug. Pumped in 9 5/8" 25 sacks cement. Pumped in 5 1/2"
4 sacks hulls, 50 sacks cement, 15 sacks Sol., 70 sacks cement, 1 hull, released
plug & followed w/ 70 sacks cement.

Maximum pressure 300 pounds

Amount of Surface Casing: 196' of 9 5/8"

I hereby certify that the above plugging instructions were given as herein stated.

Signed: [Signature]
Conservation Division Agent

I hereby state that I was not present while the above well was being plugged, however, to the best of my knowledge and belief it was plugged as herein stated. A full account for my not being present is as follows:

INVOICED

DATE 10-14-82
INV. NO. 1348-W

Signed: _____
Conservation Division Agent