

Form CP-3
Rev. 6-26-62KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSIONJ. P. Roberts
Administrator
500 Insurance Building
212 North Market
Wichita 2, Kansas

MAR 9 1964

CONSERVATION DIVISION
Wichita, KansasOperator's Full Name D. R. Lauck Oil Co., Inc.Complete Address: 301 S. Broadway, Wichita, KansasLease Name Love Well No. # 1Location NE SE SE Sec. 1 Twp. 22 Rge. 13 (E) (W)County Stafford Total Depth 3671Abandoned Oil Well X Gas Well Input Well SWD Well D & A Other well as hereafter indicated: Plugging Contractor: Glen & Smith Casing Pulling Co.Address: 204 East Sixth, Ellinwood, Kansas License No. 396Operation Completed: Hour 12:30 PM Day 6th Month March Year 1964

The Above well was plugged as follows:

420' of 8 5/8" surface pipe, cement circulated. 3658' of 5 1/2" long string,
cemented with 100 sacks. Top perforation 3312'. Plug was pushed to 3300',
and bottom was cemented with 5 sacks. Fluid was up in the hole and would
not bail down. Plug was pushed to 275', with 10' rock bridge. 5 sacks of
cement was mixed in barrel and put on plug through dump bailer, and let
set over night. Next morning hole bailed down, and 20 sacks was added to
plug. Hole was filled with mud to 40', 10' rock bridge, and cemented
with 10 sacks to base cellar. 2540' of 5 1/2" long string was recovered from
the hole.

I hereby certify that the above well was plugged as herein stated.

INVOICEDSigned: Archie Elving
Well Plugging SupervisorDATE 3/10/64INV. NO. 8750-11