

15-185-71719-0500

WELL PLUGGING RECORD

Give All Information Completely  
 Make Required Affidavit

COUNTY Stafford SEC. 34 TWP. 23 RGE. 13 E/W  
 Location as in quarters or footage from lines:  
 SW NW NW


Locate Well  
 correctly on above  
 Section Platt.

Lease Owner Petroleum Energy, Inc.  
 Lease Name Rogers Well No. 1  
 Office Address 415 First Nat'l Bk. Bldg. Wichita, KS 67202  
 Character of Well (Completed as Oil, Gas or Dry Hole):  
 Date Well Completed 12-31-82  
 Application for plugging filed 12-31-82  
 Plugging commenced 12-31-82  
 Plugging completed 12-31-82  
 Reason for abandonment of well or producing formation \_\_\_\_\_

Was permission obtained from the Conservation Division or it's  
 Agent's before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Paul Luthi  
 Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ bottom \_\_\_\_\_ T.D. 3933  
 Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out

Describe in detail the manner in which the well was plugged, indicating where the mud  
 fluid was placed and the method or methods used in introducing it into the hold. If cement  
 or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet  
 to \_\_\_\_\_ feet for each plug set.

Bottom Plug: @ 3900' w/30 sacks 50/50 pozmix, 2% gel 3% cc. thru drill pipe  
 2nd Plug: @ 720' w/ 70 sacks " " " " " " " "  
 3rd Plug: @ 320' w/40 sacks " " " " " " " "  
 Top Plug: @ 40' w/ solid bridge of 1/2 sacks hulls & 10 sacks cement  
 10 sacks cement in Rat Hole  
 5 sacks in water well

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Duke Drilling Co., Inc.

STATE OF Kansas COUNTY OF Barton, ss.  
Bill Draney (employee of owner) or (~~owner~~) of the  
 above-described well, being first duly sworn on oath, says: That I have knowledge of the  
 facts, statements, and matters herein contained and the log of the above-described well as  
 filed and that the same are true and correct. So help me God.

(Signature) Bill Draney  
 Box 823 Great Bend, KS 67530  
 (Address)

SUBSCRIBED AND SWORN TO before me this 5<sup>th</sup> day February, 19 83

STATE CORPORATION COMMISSION  
Deedee M. Hague  
 Notary Public.

My Commission expires: 4-29-86

RECEIVED  
 STATE CORPORATION COMMISSION  
 JAN 14 1983  
 CONSERVATION DIVISION  
 Wichita, Kansas

DRILLERS' WELL LOG

15-185-21719-0000

DATE COMMENCED: December 21, 1982  
DATE COMPLETED: December 31, 1982

Petroleum Energy, Inc.  
ROGERS #1  
Sec. 34, T23S, R13W  
SW NW NW  
Stafford County, Ks.

ELEVATION: 1903 K.E.

0 - 773'	Surface Soil, Sand, Shale
773 - 796'	Anhydrite
796 - 3129'	Shale & Lime
3129 - 3343'	Lime
3343 - 3360'	Shale & Lime
3360 - 3380'	Lime
3380 - 3487'	Shale
3487 - 3503'	Lime & Shale
3503 - 3764'	Lime
3764 - 3930'	Shale, Chert, Congl.
3930 - 3933'	Dolomite
3933'	RTD

FORMATION DATA

Anhydrite	773'
Topeka	3129'
Heebner	3343'
Toronto	3360'
Douglas	3380'
Br. Lime	3487'
Lansing K.C.	3503'
Base K.C.	3764'
Marnaton	3774'
Conglomerate	3809'
Viola	3832'
Simpson	3875'
Arbuckle	3930'
RTD	3933'

Surface Pipe: Set used 8-5/8",  
237 @284" w/200 sacks 60/40  
pozmix, 2% gel 3% cc.

A F F I D A V I T

STATE OF KANSAS  
COUNTY OF BARTON) ss

Bill Draney of lawful age, does swear and state that the facts and  
statements herein are true and correct to the best of his knowledge.

Bill Draney

Subscribed and sworn to before me this 5 day of January 1983.

My Comm. Expires:

4-29-86

Dorothy M. Hague  
Notary Public

RECEIVED  
STATE CONSERVATION COMMISSION

JAN 14 1983

CONSERVATION DIVISION  
Wichita, Kansas