

15-185-11467-0600

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD


FORMATION PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Reliever Report to:
Conservation Division
State Corporation Commission
800 Bittling Building
Wichita, Kansas

OR

Strike out upper line
when reporting plugging
off formations.

NORTH



Locate well correctly on above
Section Plat

Stafford County. Sec. 34 Twp. 23. Rge. 13 (E) W. (W)
Location as "NE 1/4 NW 1/4 SW 1/4" or footage from lines SE SW NW
Lease Owner Crown Oil Company, Inc., et al
Lease Name Garner Well No. 1
Office Address Box 164, Great Bend, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 8-11 1949
Application for plugging filed 8-12 1949
Application for plugging approved 8-12 1949
Plugging commenced 8-12 1949
Plugging completed 8-12 1949
Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well C. D. Stough
Producing formation Depth to top Bottom Total Depth of Well Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

3942' to 295' Heavy Rotary Mud
Plug with 15 sacks Portland cement at 295'
295' to 25' Heavy Rotary Mud
25' to top plugged with 10 sacks Portland cement

RECEIVED
Conservation Div.

AUG 26 1949

8-26-49

STATE CORPORATION
COMMISSION
KANSAS

(If additional description is necessary, use BACK of this form)
Correspondence regarding this well should be addressed to Crown Oil Company, Inc.,
Address P. O. Box 164, Great Bend, Kansas

STATE OF KANSAS COUNTY OF BARTON, ss.
E.M. Hilton H. R. Buick, Drilling Supt. (employee of owner) or (owner or operator) of the above-described well,
President being first duly sworn on oath, says: That I have knowledge of the facts, statements and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.


(Signature) E.M. Hilton

CROWN OIL COMPANY, INC., Great Bend, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 15th day of August, 1949

Henry Peacock
Notary Public.

My commission expires June 13, 1951



15-185-11467-0000

DRILLER'S LOG

COMPANY: CROWN OIL COMPANY, INC. et al LOCATION: SE SW NW 34-23S-13W
 CONTRACTOR: CROWN OIL COMPANY, INC. Stafford County,
 FARM NAME: No. 1 GARNER Kansas
 COMMENCED: 7-25-49 ELEVATION: 1902 DF
 COMPLETED: 8-11-49

CASING USED: 8-5/8" at 301' with 165 sacks

Cellar 4
 Shale and Sand 120
 Shale 220
 Shale, sand and shells 301
 Red Bed and Shale 665
 Shale 760
 Anhydrite 800
 Shale and Shells 875
 Red Bed, Shale and Shells 1210
 Shale and Shells 1285
 Salt and Shale 1390
 Shale and Shells 1620
 Lime 1900
 Broken Lime 2005
 Lime 2085
 Lime and Shale 2145
 Broken Lime 2255
 Lime and Shale 2950
 Lime and Shale Streaks 3030
 Lime and Shale 3275
 Lime 3312
 Lime and Shale 3520
 Broken Lime 3545
 Lime 3587
 Lime and Shale 3630
 Lime 3660
 Lime and Shale 3695
 Lime 3820
 Shale 3842
 Lime Cherty 3860
 Lime and Cherty 3894
 Lime 3942
 Total Depth 3942

GEOLOGICAL TOPS:
 Heebner Shale 3345 1243
 Brown Lime 3507
 Lansing (White) 3520 -1618
 Viola (chert) 3840 1938
 Simpson 3889 1987
 Arbuckle 3938 -2036

RECEIVED

-Cen- 107 DR.

AUG 26 1949

STATE OF KANSAS
COMMISSION

STATE OF KANSAS)
) SS
COUNTY OF BARTON)

I, the undersigned, being duly sworn on oath state that the above statement and log is true and a correct record and log of the well drilled at the location above described.

CROWN OIL COMPANY, INC.
By [Signature]

Subscribed and sworn to before me this 12th day of August, 1949.

[Signature]
Notary Public

My commission expires June 13, 1951.

PLUGGING
WELL NO. 54723-13W
BOOK PAGE 109 LINE 24