

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.--82-3-117

API NUMBER 15-185-21479-0000

LEASE NAME Hager

WELL NUMBER #3

 Ft. from S Section Line

 Ft. from E Section Line
C N/2 NE

SEC. 33 TWP. 23 RGE. 13W (E) or (W)

COUNTY Stafford

Date Well Completed 9-29-81

Plugging Commenced 9-1-87

Plugging Completed 9-8-87

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Davis Petroleum, Inc.

ADDRESS Rt. 1 Box 183B
Great Bend, Kansas 67530

PHONE # (316) 793-5831 OPERATORS LICENSE NO. 4656

Character of Well SWD

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC District Office prior to plugging this well? Yes

Which KCC Office did you notify? Dist. #1 Dodge City, Kansas

Is ACO-1 filed? If not, is well log attached?

Producing Formation Depth to Top Bottom T.D. 4150'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8-5/8"	342'	none
				5-1/2"	3997'	2720'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

Plugged off bottom with sand to 3945' and 5 sacks cement. Shot pipe @3005',
2920', 2720', pulled a total of 67 joints of 5-1/2" casing. Plugged surface
with 3 hulls, 10 gel, 50 cement, 10 gel, 1 hull, released plug and 125 cement,
60/40 pos, 6% gel. Plugging Complete.
(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Kelso Casing Pulling, Inc. License No. 6050

Address P.O. Box 347 Chase, Kansas 67524

STATE OF Kansas COUNTY OF Rice, ss.

Mike Kelso, Vice-President (Employee of Operator) or (Operator) of

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well and that the same are true and correct, so help me God.

(Signature) Mike Kelso

(Address) Box 347 Chase, Kansas 67524

SUBSCRIBED AND SWORN TO before me this 10th day of Sept., 1987

Irene Hoover
Notary Public

My Commission Expires:



RECEIVED
STATE CORPORATION COMMISSION
9-2-87
SEE OPERATOR'S LOG
CONSERVATION DIVISION
Wichita, Kansas

DRILLERS WELL LOG

SWPW

15-185-21479-0550

HAGER #3
C-N $\frac{1}{2}$ -NE
SEC. 33-23-13
Stafford County, Kansas

T.D. 4150'
Elevation 1904' K.B.

Commenced: 9-19-81
Completed: 9-29-81

CASING:

8 5/8" Set at 342'
5 1/2" Set at 3997.50

CEMENT:

W/300 SX 50/50 Pozmix 2% Gel 3% CC
W/150 SX 50/50 Pozmix 10% Salt
3/4 CFR 2

DEPTH:

0-100
100-133
133-773
773-800
800-1280
1280-1479
1479-4150
RTD 4150

FORMATION:

Sand and Shell
Sand
Blue Shale and Red Beds
Anhy
Shale and Shells
Shale
Lime and Shale

FORMATION TOPS:

Brown Lime 3493
Lansing 3517
Base K.C. 3747
Viola 3846
Simp. Shale 3890
Arbuckle 3944
R.T.D. 4150

AFFIDAVIT

STATE OF KANSAS)
) SS:
COUNTY OF BARTON)

I certify that this is a true and correct copy of the above log to the best of my knowledge.


L. D. DRILLING, INC.

Don Popp
DON POPP

SWORN to and subscribed before me this ____ day of October, 1981.

My Appointment Expires: 5-20-85

Bessie DeWerff
BESSIE DeWERFF



RECEIVED
STATE CORPORATION COMMISSION

AUG 27 1981

LABORATORY DIVISION
Topeka, Kansas

Davis Petroleum / R. S. Searle