

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-185-21391-0000

LEASE NAME Hager

WELL NUMBER #2

 Ft. from S Section Line

 Ft. from E Section Line
C S/2 NE

SEC. 33 TWP. 23 RGE. 13W (E) or (W)

COUNTY Stafford

Date Well Completed 8-21-81

Plugging Commenced 8-27-87

Plugging Completed 9-8-87

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Davis Petroleum, Inc.

ADDRESS Rt. #1 Box 183B
Great Bend, Kansas 67530

PHONE#(316) 793-5831 OPERATORS LICENSE NO. 4656

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC District Office prior to plugging this well? Yes

Which KCC Office did you notify? Dist. #1 Dodge City, Kansas

Is ACO-1 filed? If not, is well log attached?

Producing Formation Depth to Top Bottom T.D. 3924'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8-5/8"	338'	none
				5-1/2"	3923'	2948'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

Plugged off bottom with sand to 3475' and 5 sacks cement. Shot pipe @3000', 2948', pulled a total of 72 joints of 5-1/2" casing. Plugged surface with 3 hulls, 10 gel, 50 cement, 10 cement, 1 hull, released plug and 125 cement, 60/40 pos, 6% gel. Plugging Complete.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Kelso Casing Pulling, Inc. License No. 6050 RECEIVED

Address P.O. Box 347 Chase, Kansas 67524 COMMISSION

STATE OF Kansas COUNTY OF Rice, ss. SEP 14 1987

Mike Kelso, Vice-President

(Employee of Operator) or (Operator) or (Division) of

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.


(Signature) Mike Kelso

(Address) Box 347 Chase, Kansas 67524

SUBSCRIBED AND SWORN TO before me this 10th day of Sept., 1987

James Hoover
Notary Public

My Commission Expires:



DRILLERS WELL LOG

L. D. DRILLING, INC. - CONTRACTOR L. D. DAVIS - OPERATOR

15-185-21391-000

HAGER # 2
C. S. 1/2 NE
Sec. 33-23-13
Stafford County, Kans

T. D. 3924'
ELEV. 1906 K.B.

COMMENCED: 8-14-81
COMPLETED: 8-21-81

CASING

CEMENT

8 5/8" set at 338'
5 1/2" set at 3923' (1 ft. off bottom (17.02 Shoe Joint))
W/300 sx. 50/50 Pozmix, 2% Gel, 3% CC
W/150 sx. 50/50 Pozmix, 1 1/2% Salt Sat.
3 1/4% CFR2

FORMATION

DEPTH

Sand	0 - 100
Shale	100 - 341
Red Bed	341 - 769
Anhy.	379 - 792
Shale w/shells	792 - 905
Shale	905 - 1640
Lime & Shale	1640 - 3924
R.T.D.	3924

FORMATION TOPS

Heebner	3336 (-1430)
Toronto	3357 (-1451)
Douglas	3375 (-1469)
Brown Lime	3475 (-1569)
Lansing K/C	3502 (-1596)
Viola	3839 (-1933)
Simp. Shale	3868 (-1962)
Simp. Sand	3888 (-1982)
Arbuckle	3918 (-2012)
R.T.D.	3924 (-2018)

AFFIDAVIT

STATE OF KANSAS }
COUNTY OF BARTON } ss

I certify that this is a true and correct copy of the above log to the best of my knowledge.

L. D. DRILLING, INC

Don Popp


Don Popp

Sworn to and subscribed before me this 28th day of August, 1981.

My appointment expires: 5-20-85

Bessie M. DeWerff

Bessie DeWerff, Notary Public



STATE COMMISSION

AUG 27 1981

NOTARY PUBLIC
STATE OF KANSAS

Davis Petroleum / Per Danell