

15-185-12770-0000


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

Stafford County, Sec. 33 Twp. 23 Rge. 13 (E) W (W)

Location as "NE/CNW/SW" or footage from lines Approx. SW NW SE
Lease Owner Lotus Oil Company (Crown Oil Co., Inc.)
Lease Name V. F. W. Well No. 2
Office Address P. O. Box 164 Great Bend, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Oil
Date well completed 3-15-50 19
Application for plugging filed 12-14-53 19
Application for plugging approved 12-15-53 19
Plugging commenced 12-17-53 19
Plugging completed 1-4-54 19
Reason for abandonment of well or producing formation _____



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production April 24 1953
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well M. A. Rives
Producing formation Arbuckle Depth to top 3920' Bottom 3930' Total Depth of Well 3970' Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	357'	
				5-1/2"	3970'	3018'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Measured in to total depth 3970' - plugged back to 3915' with crushed rock and 5 sacks cement. Shot casing at 3000' - pulled casing out of hole. Pumped in 30 sacks mud and squeezed surface casing with 100 sacks cement.

Work started 12-17-53; completed 1-4-54. Cement plug stopped at 327'.

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor J. O. Forbes - Forbes Casing Pulling Company
Address P. O. Box 221 Great Bend, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.
J. L. Haines (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) J. L. Haines
P. O. Box 164, Great Bend, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 26th day of January, 1954
Emma Jean Sanger Notary Public.

My commission expires August 29, 1955

PLUGGING
FILE SEC 33 T 23 R 13W
BOOK PAGE 49 LINE 25

1-27-54

DRILLER'S LOG

15-185-12770-0000

COMPANY: CROWN OIL COMPANY, INC. LOCATION: App. SW NW SE, 33-23-13W
 CONTRACTOR: HILTON DRILLING COMPANY, INC. Stafford County, Kansas
 FARM NAME: V.F.W. #2 ELEVATION: 1907 D.F.
 COMMENCED: 2-28-50 CASING USED: 3-5/8" at 357 feet with 225 sacks
 COMPLETED: 3-15-50 5-1/2" at 3970 feet with 125 sacks

Cellar	4	Lime and Sand	3847
Sand, Gravel, Red Bed	357	Lime	3874
Red Bed and Shale	770	Shale and Sand	3906
Anhydrite	795	Lime	3931
Shale, Shells and Salt	1030	Lime	3957
Shale and Shells	1350	Lime	3970
Shale and Shells	1625		
Shale, Lime and Shells	1700	<u>Total Depth</u>	<u>3970</u>
Lime	1745		
Broken Lime	1900		
Lime	1990		
Lime	2105		
Lime	2190		
Lime	2285		
Lime	2415		
Lime	2550		
Shale and Lime	2630		
Shale and Lime	2770		
Shale and Lime	2920		
Shale and Lime	3020		
Shale and Broken Lime	3135		
Lime	3150		
Lime	3212		
Lime and Shale	3292		
Lime and Shale	3340		
Lime and Shale	3380		
Lime and Shale	3440		
Lime and Shale	3482		
Lime	3527		
Lime	3562		
Lime	3595		
Lime	3626		
Lime	3641		
Lime	3682		
Lime	3711		
Lime	3745		
Lime	3784		
Lime	3812		

GEOLOGICAL TOPS

Heebner Shale	3342
Brown Lime	3482
Lansing (White)	3507
Viola	3827
Simpson	3871
Arbuckle	3927

STATE OF KANSAS)
) SS
 COUNTY OF BARTON)

I, the undersigned, being duly sworn on oath, state that the above statement and log are true and correct record and log of the well drilled at the location above described.

HILTON DRILLING COMPANY, INC.

By _____

Subscribed and sworn before me this 28th day of March, 1950.

PLUGGING
 FILE SEC 33-T-23 R/3W
 BOOK PAGE 149 LINE 25

 Notary Public

My commission expires June 13, 1951.