


15-185-02769-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail - Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

WELL PLUGGING RECORD

Stafford County. Sec. 33 Twp. 23 Rge. 13 (E) W (W)
Location as "NE/CNW/SW" or footage from lines SE NW SE
Lease Owner Lotus Oil Co. (Crown Oil Co., Inc.)
Lease Name V. F. W. Well No. 1
Office Address P. O. Box 164 Great Bend, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) _____
Date well completed 1-1-50 19____
Application for plugging filed 12-14-53 19____
Application for plugging approved 12-15-53 19____
Plugging commenced 12-22-53 19____
Plugging completed 12-31-53 19____
Reason for abandonment of well or producing formation _____



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production Oct. 7 1953
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well M. A. Rives
Producing formation Arbuckle Depth to top 3930' Bottom 3955' Total Depth of Well 3955' Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8- 5/8	330	
				5-1/2	3955	2928'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Measured in to total depth 3955' - plugged back to 3930' with crushed rock and 5 sacks cement. Shot casing at 2918' - pulled casing out of hole.

Pumped in 30 sacks mud - 10 sacks mud and squeezed surface casing with 100 sacks cement.

Work started 12-22-53; completed 12-31-53. Cement plug stopped at 319'.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor J. O. Forbes - Forbes Casing Pulling Co.
Address P. O. Box 221 Great Bend, Kansas.

STATE OF Kansas, COUNTY OF Barton, ss.

J. L. Haines (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) _____

P. O. Box 164, Great Bend, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 26th day of January, 1954

Emma Jean Sayre Notary Public.

My commission expires August 29, 1955

24-7368-6 3-53-20M

PLUGGING
FILE SEC 33 T 23 R 13W
BOOK PAGE 149 LINE 24

1-27-54

15-185-12769-0000

D R I L L E R ' S L O G

COMPANY: CROWN OIL COMPANY, INC.

LOCATION: N/2 Lot 3, Higgins subdivision
SE NW SE 33-23-13W
Stafford County, Kansas

CONTRACTOR: HILTON DRILLING COMPANY, INC.

FARM NAME: VFW #1

ELEVATION: 1906 DF

COMMENCED: 12-11-49

Completed: 1-1-50

CASING USED: 8-5/8" at 300 feet with 225 sacks
5-1/2" at 3955' with 125 sacks

Cellar	4
Surface Clay and Sand	110
Lime stone Shale	195
Shale and Red Bed	270
Shale and Shells	300
Red Bed	323
Red Bed	475
Red Bed and Shale	760
Anhydrite	790
Shale	940
Shells and Shale	1310
Shells and Shale	1650
Lime	1735
Shale and Lime	2035
Broken Lime and Shale	2250
Lime and Shale	2340
Broken Lime and Shale	2535
Lime and Shale	3195
Lime	3253
Lime	3305
Lime and Shale	3340
Lime	3363
Lime and Shale	3470
Lime	3697
Shale and Lime	3754

Lime	3807
Lime and Chert	3853
Lime and Chert	3875
Shale	3901
Shale and Lime	3920
Lime	3955
<u>Total Depth</u>	<u>3955</u>

GEOLOGICAL TOPS

Heebner	3336 (-1428)
Toronto	3360 (-1452)
Brown Lime	3471 (-1563)
Lansing	3499 (-1591)
Conglomerate	3816 (-1908)
Viola	3821 (-1913)
Simpson	3879 (-1971)
Sand	3900 to 3910
Arbuckle	3930 (-2022)
T.D.	3946 (-2038)

STATE OF KANSAS)
) SS
COUNTY OF BARTON)

I, the undersigned, being duly sworn on oath, state that the above statement and log are true and a correct record and log of the well drilled at the location above described.

CROWN OIL COMPANY, INC.

Subscribed and sworn to before me this 23rd day of January, 1950.

Notary Public

My commission expires: June 13, 1951.

Copy

PLUGGING
R/W SEC 33 T 23 R 13W
ROCK PAGE 149 LINE 24