

STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

OR

FORMATION PLUGGING RECORD

Strike out upper line  
when reporting plug-  
ging off formations.

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Bittling Building  
Wichita, Kansas

Stafford County. Sec. 33 Twp. 23 Rge. (E) 13 (W)

Location as "NE $\frac{1}{4}$ NW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines NW NW SE  
Lease Owner Crown Oil Company, Inc.  
Lease Name Ring Well No. 1  
Office Address Box 164, Great Bend, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) oil well  
Date well completed February 27, 19 50  
Application for plugging filed June 11, 19 50  
Application for plugging approved June 11, 19 50  
Plugging commenced June 11, 19 50  
Plugging completed June 11, 19 50  
Reason for abandonment of well or producing formation Fluid turned to water and after workover, failed to make a commercial producer  
If a producing well is abandoned, date of last production No production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

NORTH

		X	

Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well C. D. Stough  
Producing formation..... Depth to top..... Bottom..... Total Depth of Well 3980 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from..... feet to..... feet for each plug set.

Lane Wells Plug set at 3721'; filled from 3721' to 3620' with sand; from 3620' to 3585' with 5 sacks cement; from 3585' to 355' with heavy mud; from 355' to 340' with rock bridge; from 340' to 300' with 25 sacks of cement; from 300' to 30' with heavy mud; and from 30' to top of ground with 10 sacks of cement.

FILED  
JUL 1 - 1950 7-1-50  
STATE CORPORATION  
COMMISSION  
KANSAS

(If additional description is necessary, use BACK of this sheet)  
Correspondence regarding this well should be addressed to Crown Oil Company, Inc.  
Address Box 164, Great Bend, Kansas

STATE OF KANSAS, COUNTY OF BARTON, ss.  
E. M. Hilton, President (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.  
(Signature) By: E. M. Hilton President  
Box 164, Great Bend, Kansas (Address)

SUBSCRIBED AND SWORN to before me this 29th day of June, 19 50  
My commission expires June 13, 1951.

PLUGGING  
NW SEC 33 Twp 23 R 13  
BOOK PAGE 11 LINE 29

*[Signature]*  
Notary Public.

D R I L L E R ' S   L O G

15-185-114680000

COMPANY: CROWN OIL COMPANY, INC.                      LOCATION: NW NW SE 33-23-13W  
 CONTRACTOR: HILTON DRILLING COMPANY, INC.                      Stafford County, Kansas

FARM NAME: Ring #1

COMMENCED: February 11, 1950                      CASING USED: 8-5/8" at 356' with 240 sacks  
 COMPLETED: February 27, 1950                      5-1/2" at 3980' with 125 sacks

Cellar	4	Lime	3669
Sand	130	Lime	3695
Sand	150	Lime	3720
Blue Shale	180	Lime	3743
Clay and Shells	245	Lime	3789
Sand	286	Lime	3820
Red Bed	357	Lime, Sand and Chert	3855
Red Bed	480	Lime and Shale	3880
Shale	590	Shale and Sand	3903
Shale	776	Lime	3939
Anhydrite	795	Lime	3973
Shale and Shells	860	Lime	3980
Shale and Shells	1170		
Salt	1200		
Salt, Shale and Shells	1465		
Shale and Shells	1675		
Lime	1775		
Lime	1875		
Lime	1935		
Lime and Shale	2075		
Brown Lime	2175	Heebner Shale	3345
Lime and Shale	2265	Lansing (white)	3511
Lime and Shale	2348	Viola	3835
Brown Lime and Shale	2475	Simpson	3877
Lime and Shale	2590	Arbuckle	3924
Lime and Shale	2715		
Lime and Shale	2825		
Lime and Shale	2920		
Lime and Shale	2995		
Brown Lime and Shale	3090		
Lime and Shale	3160		
Lime and Shale	3235		
Lime	3310		
Lime and Shale	3352		
Lime and Shale	3391		
Lime and Shale	3463		
Lime	3522		
Lime	3556		
Lime	3575		
Lime	3600		
Lime	3637		

STATE OF KANSAS        )  
                                       )   SS  
 COUNTY OF BARTON    )

I, the undersigned, being duly sworn on oath, state that the above statement and log are true and correct record and log of the well drilled at the location above described.

HILTON DRILLING COMPANY, INC.

By *J. R. Buick*

Subscribed and sworn before me this 14th day of March, 1950.

*Henry Pearce*

My commission expires June 13, 1951.

PLUGGING LOG  
 FOR WELLS IN THE STATE OF KANSAS  
 BOOK PAGE 11 LINE 29  
 MAR 16 1950  
 REGISTRATION  
 SECTION