

15-185-61325-0000


STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas 67202

WELL PLUGGING RECORD

STAFFORD County, Sec. 33 Twp. 23S Rge. (E) 13 (W)
Location as "NE/CNW/SW" or footage from lines SE SE NE
Lease Owner MORRIS GARVIN
Lease Name DELKER Well No. 1
Office Address ST. JOHN, KANSAS 67576
Character of Well (completed as Oil, Gas or Dry Hole) OIL
Date well completed _____ 19____
Application for plugging filed JANUARY 24 19 72
Application for plugging approved _____ 19____
Plugging commenced JANUARY 25 19 72
Plugging completed FEBRUARY 18 19 72
Reason for abandonment of well or producing formation DEPLETED



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? YES

Name of Conservation Agent who supervised plugging of this well RUSSELL BIBERSTEIN
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3921 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				13"	259'	NONE
				5 1/2"	3921'	1666.77'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

3921' - 3750' - PLUG
3750' - 3680' - SAND
3680' - 3640' - 5 SACKS CEMENT
3640' - BASE - PUMPED 100 SACKS CEMENT - 15 SACKS GEL AND 3 SACKS HULLS.

RECEIVED
STATE CORPORATION COMMISSION
FEB 28 1972
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor SANTA-FE PIPE & SUPPLY, INC.
Address BOX 562 - GREAT BEND, KANSAS 67530

STATE OF KANSAS, COUNTY OF BARTON, ss. T. L. NUTT

(employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) [Signature]

BOX 562 - GREAT BEND, KANSAS 67530
(Address)

SUBSCRIBED AND SWORN TO before me this 24th day of February, 19 72

My commission expires July 31, 1974
Mary M. Guesnier
Mary M. Guesnier Notary Public.

WELL LOG BUREAU -- KANSAS GEOLOGICAL SOCIETY
412 Union National Bk. Bldg., Wichita, Kansas

15-185-01375-0600

COPY

Company - STANOLIND OIL & GAS CO.
Farm - Fred W. Delker No. 1


Morris Garvin

SEC. 33 T. 23 R. 13 W
SE SE NE
330' N SL 2310' E WL NE¹

DISCOVERY WELL

Total Depth. 3924'
Comm. 4-16-44 Comp. 5-6-44
Shot or Treated.
Contractor.
Issued. 7-1-44 Rotary O-3924

County. Stafford
KANSAS



CASING:
13" 258' 9" Cam. 300 *24*
5 1/2" 3920' 11" Cam. 100 *24*

Elevation. 1900' DI

Production. Pot. 2359 B. 5% wtr.

Figures Indicate Bottom of Formations.

cellar	7 1/2
sand	120
shale	150
shale & shells	286
sand	420
red sdy shale	765
anhydrite	820
shale & shells	850
shale, shells & red bed.	975
shale & lime	1075
shale & lime shells	1140
red bed shale	1155
shale & lime shells	1325
shale, lime & salt	1635
shale & shells	1715
anhydrite	1765
shale & lime shells	1795
shale & lime	1950
brkn, shale & lime	1970
lime	2070
shale & lime	2217
lime brkn & shale	2295
shale & lime	3150
lime	3195
shale & lime	3295
lime	3425
shale	3472
shale & lime	3519
lime	3781
cherty lime	3855
cherty conglomerate	3870
shale & lime	3896
dolomite	3901
3901 corr. to 3899	
shale	3919
lime	3924
Total Depth.	
Tops:	
Lansing	3500
Viola	3828
Simpson	3891
Arbuckle	3919

RECEIVED
STATE CORPORATION COMMISSION
JAN 27 1972
CONSERVATION DIVISION
Wichita, Kansas