

15-185-11460-0000


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

FORMATION PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

Strike out upper line
when reporting plug-
ging of formations.



Stafford County. Sec. 32 Twp. 23 Rge 13 (E) W (W)
Location as "NE1/4NW1/4SW1/4" or footage from lines NWC SE
Lease Owner Crown Oil Company, Inc. et al
Lease Name Gray-Gillmore Well No. 1
Office Address 2421 Tenth Street, Great Bend, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed May 25 19 49
Application for plugging filed May 25 19 49
Application for plugging approved May 25 19 49
Plugging commenced May 25 19 49
Plugging completed May 25 19 49
Reason for abandonment of well or producing formation Dry

Locate well correctly on above
Section Plat

Name of Conservation Agent who supervised plugging of this well C. D. Stough
Producing formation Depth to top Bottom Total Depth of Well 4056 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

4056' to 319' Heavy Rotary Mud
Plug with 15 sacks Portland cement at 319'
319' to 35' Heavy Rotary Mud
35' to Top plug with 10 sacks Portland cement

6-1-49

RECEIVED
Conservation Div.
JUN - 1 1949
STATE CORPORATION
COMMISSION
KANSAS

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to Crown Oil Company, Inc.,
Address P. O. Box 164, Great Bend, Kansas

STATE OF KANSAS, COUNTY OF BARTON, ss.

H. R. Buick, Drilling Supt. (employee of owner) or (owner or operator) of the above-described well,
being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) *H. R. Buick*

CROWN OIL COMPANY, INC., Great Bend, Kans.
(Address)

SUBSCRIBED AND SWORN TO before me this 26th day of May, 19 49

Henry Pacas
Notary Public.

My commission expires June 13, 1951

22-2626 2-48-15M
PLUGGING
FILE SEC 37 T 23 R 13W
BOOK PAGE 99 LINE 6

15-185-11460-0000

DRILLER'S LOG

COMPANY: CROWN OIL COMPANY, INC.
THE LOTUS OIL COMPANY

LOCATION: NWC SE 32-23S-13W
Stafford County,
Kansas

CONTRACTOR: CROWN OIL COMPANY, INC.
FARM NAME: No. 1 Gray-Gillmore

ELEVATION: 1911 D.F.

COMMENCED: 5-4-49
COMPLETED: 5-26-49

CASING USED: 8-5/8" at 319' with 175 sacks

Cellar	4
Surface Clay and Sand	65
Surface Sand and Shale	319
Red Bed	345
Red Bed and Shale	550
Red Bed Shale and Shell	787
Anhydrite	819
Shale and Shells	1290
Shale, Shells and Salt	1580
Shale and Shells	1665
Broken Lime	1730
Lime	1927
Broken Lime	2065
Lime	2200
Lime and Shale Streaks	2295
Lime and Shale	2895
Broken Lime	3020
Lime	3077
Lime and Shale	3210
Lime	3455
Shale and Lime	3600
Lime	3807
Cherty Lime	3830
Lime	3893
Lime Chert	3968
Lime	4005
Lime and Shale	4029
Chert & Lime	4056
Total Depth	4056

GEOLOGICAL TOPS:

Heebner Shale	3380
White Lansing	3544
Viola	3900
Simpson	3984
Simpson Sand	3996-4002
Arbuckle	4044

RECEIVED

Conservation Div.


JUN - 1 1949

STATE CORPORATION
COMMISSION
KANSAS

STATE OF KANSAS)
) SS
COUNTY OF BARTON)

I, the undersigned, being duly sworn on oath state that the above statement and log is true and a correct record and log of the well drilled at the location above-described.

CROWN OIL COMPANY, INC.



By [Signature]
Vice President

Subscribed and sworn to before me this 26th day of May, 1949.

[Signature]
Notary Public

My Commission expires June 13, 1951.