

15-185-11458-0000

WELL PLUGGING RECORD

STATE OF KANSAS STATE CORPORATION COMMISSION

Give All Information Completely Make Required Affidavit Mail or Deliver Report to: Conservation Division State Corporation Commission 800 Bittling Building Wichita, Kansas


OR

Strike out upper line when reporting plugging of formations.

FORMATION PLUGGING RECORD

Stafford County Sec. 32 Twp. 23S Rge. 13 (E) W (W) Location as "NE 1/4 NW 1/4 SW 1/4" or footage from lines NW SE NW 1/4 Lease Owner Crown Oil Company, et al Lease Name Bell Well No. 2 Office Address Odell at Tenth Street, Great Bend, Kansas Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole Date well completed September 27 1949 Application for plugging filed September 27 1949 Application for plugging approved September 27 1949 Plugging commenced September 27 1949 Plugging completed September 27 1949 Reason for abandonment of well or producing formation If a producing well is abandoned, date of last production 19 Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

NORTH



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well Producing formation Depth to top Bottom Total Depth of Well Feet Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Table with 7 columns: Formation, Content, From, To, Size, Put In, Pulled Out

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set. 3785 to 347' Heavy Rotary Mud 347' with 15 sacks Portland Cement 347' to 30' Heavy Rotary Mud 30' to top plugged with 10 sacks Portland Cement

10-1-49

RECEIVED Conservation Div. OCT 1 X 1949 STATE CORPORATION COMMISSION KANSAS

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to Crown Oil Company, Inc. Address Box 164, Great Bend, Kansas


STATE OF KANSAS, COUNTY OF BARTON, ss. H. R. Buick, Drilling Superintendent (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) H. R. Buick CROWN OIL COMPANY, INC., Great Bend, Kansas (Address)

SUBSCRIBED AND SWORN to before me this 29th day of September, 1949 Henry Pascoe Notary Public

My commission expires June 13, 1951.

22-2625 2-48-15M



15-185-11458-0000

D R I L L E R ' S L O G

COMPANY: CROWN OIL COMPANY, INC. et al

LOCATION: NW SE NW 32-23S-13W
Stafford County, Kansas

CONTRACTOR: HILTON DRILLING COMPANY, INC.

ELEVATION: 1902 DF

FARM NAME: BELL NO. 2

COMMENCED: 9-13-49

COMPLETED: 9-27-49

CASING USED 8-5/8" at 347' with 225 sacks

Cellar	4
Surface Clay and Sand	130
Blue Clay	215
Red Bed	260
Sand and Gravel	305
Red Bed	347
Red Bed and Shale	485
Red Bed, Shale and Shells	785
Anhydrite	810
Shale and Shells	1250
Salt	1300
Shale and Shells	1425
Lime and Shale	1665
Broken Lime	1770
Lime	1975
Lime and Shale	2055
Lime and Shale	2815
Lime and Shale Broken	2925
Shale and Lime	3005
Lime and Shale	3105
Lime and Shale Broken	3195
Lime	3275
Lime and Shale Streaks	3305
Shale and Lime	3625
Lime	3785
Total Depth	3785

STATE OF KANSAS)
) SS
COUNTY OF BARTON)

I, the undersigned, being duly sworn on oath, state that the above statement and log are true and a correct record and log of the well drilled at the location above described.

HILTON DRILLING COMPANY, INC.

By

[Handwritten Signature]

Subscribed and sworn to before me this 27th day of September, 1949.

[Handwritten Signature]
Notary Public

My Commission Expires June 13, 1951.

RECEIVED
Conservation Div.
OCT 1 X 1949
STATE CORPORATION
COMMISSION
KANSAS

PLUGGING
WELL SEC 32 T 23 R 13 W
BOOK PAGE 17 LINE 13