

15-185-11457-0000

STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Bittling Building  
Wichita, Kansas

OR  
FORMATION PLUGGING RECORD

Strike out upper line  
when reporting plug-  
ging off formations.

Stafford County. Sec. 32 Twp. 23 Rge. 13 (E) W (W)  
Location as "NE $\frac{1}{4}$ NW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines SE SW NW  
Lease Owner Crown Oil Company, Inc.  
Lease Name Bell Well No. 3  
Office Address Odell at Tenth, Great Bend, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed November 21 19 49  
Application for plugging filed December 2 19 49  
Application for plugging approved December 2 19 49  
Plugging commenced December 9 19 49  
Plugging completed December 9 19 49  
Reason for abandonment of well or producing formation  
If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was com-  
menced?

NORTH


Locate well correctly on above  
Section Plat

Name of Conservation Agent who supervised plugging of this well  
Producing formation Depth to top Bottom Total Depth of Well Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

3684' to 3670 Plug with 5 sacks Cement  
Heavy Rotary Mud to 321'  
Plug with 15 sacks  
Heavy Rotary Mud to 40'  
40' to Surface Plug and 10 sacks

DEC 15 1949

12-15-49

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to Crown Oil Company, Inc.  
Address Box 164, Great Bend, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.  
H. R. Buick (employee of owner) or (owner or operator) of the above-described well,  
being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) H. R. Buick


St. John, Kansas (Address)

SUBSCRIBED AND SWORN to before me this 14th day of December, 19 49.

Edwina Elder

Notary Public.

My commission expires September 21, 1953



15-185-11457-0000

D R I L L E R ' S   L O G

COMPANY: CROWN OIL COMPANY, INC.  
CONTRACTOR: HILTON DRILLING COMPANY, INC.  
FARM NAME: BELL NO. 3  
COMMENCED: 11-7-49  
COMPLETED: 11-21-49

LOCATION: SE SW NW 32-23-13W  
Stafford County, Kansas  
ELEVATION: 1907 DF

CASING USED: 8-5/8" at 320' with 220 sacks  
5 1/2" at 3676' with 50 sacks

Sand, Surface Clay	100
Sand	130
Shale	210
Red Bed	260
Sand	305
Red Bed and Shells	320
Red Bed	510
Red Bed - Shale	793
Anhydrite	820
Shale and Shells	1120
Shale	1140
Shale - Lime	1695
Lime	1825
Lime Broken	1870
Lime	2025
Broken Lime and Shale	2100
Lime	2130
Broken Lime	2230
Lime	2305
Lime and Shale	2365
Lime	2440
Shale	2465
Shale and Lime	2640
Broken Lime and Shale	2855
Lime and Shale	3205
Broken Lime and Shale	3260
Lime and Shale	3295
Lime	3353
Lime and Shale	3430
Lime	3525
Lime and Shale	3628
Lime	3684
Total Depth	3684

RECORDED

PLUGGING  
FILE SEC 32 R 23 P 130  
BOOK PAGE 49 LINE 3  
KANSAS

STATE OF KANSAS )  
                          ) SS  
COUNTY OF BARTON )

I, the undersigned, being duly sworn on oath, state that the above statement and log are true and a correct record and log of the well drilled at the location above described.

HILTON DRILLING COMPANY, INC.

By W. P. Reich

Subscribed and sworn to before me this 25th day of November, 1949.

Henry Peacock  
Notary Public

My commission expires June 13, 1951.