

15-185-10955-0000

STATE OF KANSAS  
STATE CORPORATION COMMISSION

Form CP-4

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 No. Market  
Wichita, Kansas

Stafford County. Sec. 32 Twp. 23 Rge. 13 (E) (W)

Location as "NE/CNW%SW%" or footage from lines SW NE SW

Lease Owner W.R. Gross

Lease Name Williams Well No. 5

Office Address Box 510 El Dorado, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Oil Well

Date well completed 1-27-50 19

Application for plugging filed 12-7-66 19

Application for plugging approved 12-9-66 19


Plugging commenced 12-12-66 19

Plugging completed 12-16-66 19

Reason for abandonment of well or producing formation depleted

If a producing well is abandoned, date of last production \_\_\_\_\_ 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well Archie Elving

Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3673 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	345'	none
				5 1/2	3667'	1500'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Set 15' rock bridge at 3290' and dump 5 sacks of cement

Set 15' rock bridge from 300' to 285' and mixed and dumped 5 sacks of cement, let set overnight

Bailed hole dry to bridge and dump 20 sacks of cement

Mud hole to 40', rock to 30' and dump 10 sacks of cement to surface

10-4-66  
DEC 29 1966

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Flint Engineering and Const. Co. **CONSERVATION DIVISION**  
**Wichita, Kansas**

Address 2375 W. Central El Dorado, Kansas

STATE OF Kansas, COUNTY OF Butler, ss.

\_\_\_\_\_, (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) James Davis

SUBSCRIBED AND SWORN TO before me this 21 day of December, 19 66

My commission expires Sept. 27, 1967

Ronald R. Hanson  
Notary Public.

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY  
 508 E. Murdock, Wichita, Kansas


15-185-10955-0000

Company - CROWN OIL CO. & LOTUS OIL CO.  
 Farm - Williams No. 5

SEC. 32 T. 23 R. 13W  
 SW NE SW

Total Depth. 3673  
 Comm. 1-15-50 Comp. 1-27-50  
 Shot or Treated.  
 Contractor. Crown Oil Co.  
 Issued. 10-21-50

County. Stafford  
 KANSAS



Elevation. 1910 D.E.

Production. Phys. 1393 bbls.

CASINGS:

8 5/8" 345' cem. w/225 sx.  
 5 1/2" 3667' cem. w/100 sx.

Figures Indicate Bottom of Formation

cellar	4
surface clay & sand	150
shale blue	200
clay & shells	220
clay	260
sand & shells	310
red bed	345
red bed & shale	785
anhyd.	825
shale & shells	1680
lime	1785
lime brkn	1920
lime & shale	2025
lime brkn	2235
lime & shale	2730
shale, lime & shells	2885
lime brkn & shale	3030
lime & shale	3090
lime brkn & lime	3160
lime brkn & shale	3230
lime	3409
lime & shale	3525
lime	3673
Total Depth	

Tops:	
Heebner shale	3383
Lansing white	3540
Pay zone	3668

RECEIVED  
 CONSERVATION DIVISION  
 WICHITA, KANSAS  
 DEC 22 1966