


STATE OF KANSAS  
STATE CORPORATION COMMISSION

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Bittling Building  
Wichita, Kansas

WELL PLUGGING RECORD

STAFFORD County. Sec. 4 Twp. 22 Rge. (E) 13 (W)  
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines NW NW SE  
Lease Owner E. H. Adair & O. E. Bedell  
Lease Name Viola Moon Well No. 1  
Office Address 407 W-K-H Building  
Character of Well (completed as Oil, Gas or Dry Hole) Oil  
Date well completed September 17, 1948  
Application for plugging filed February 25, 1951  
Application for plugging approved February 25, 1951  
Plugging commenced February 25, 1951  
Plugging completed February 25, 1951  
Reason for abandonment of well or producing formation 7 bbls. water per hr.  
 $\frac{1}{2}$  bbl. of oil.  
If a producing well is abandoned, date of last production November 1950  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes



Locate well correctly on above Section Flat

Name of Conservation Agent who supervised plugging of this well C. D. Stough, Great Bend, Kansas  
Producing formation Depth to top Bottom Total Depth of Well 3802 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
Copy of Well Log attached.						

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled hole with mud to 340' put in 15' rock bridge, dumped 15 sx of cement, added hole to 25' of surface, dumped 10 sx cement, filled to surface.

RECEIVED  
STATE CORPORATION COMMISSION

MAR 22 1951

3-22-51

CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to E. H. Adair Oil Company  
Address 407 W-K-H Building  
Wichita 2, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.

E. H. Adair (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) [Signature]

Wichita, Kansas

(Address)

SUBSCRIBED AND SWORN TO before me this 8th day of March, 1951.

[Signature]

Notary Public.

My commission expires September 15, 1953

PLUGGING  
FILE SEC 4T 22R 13W  
BOOK PAGE 649

V. MOON WELL #1

Location: NW NW SE  
 Sec. 4-22-13  
 Stafford County, Kansas

Commenced: 9/4/48

Completed: 9/17/48

Operator: E. H. Adair Oil Company

Production:

Contractor: Shawver-Graham, Inc.

Casing Record: 255 Ft. of 8" Surface Pipe  
 Cemented with 250 sacks cement and 5' acquagel

3760' of 5" O.D. Casing  
 Cemented with 125 Sacks of Cement

LOG

(Figures indicate bottom of formation)

Sand	167
Sand Shell	255
Red Bed	720
Red Rock	800
Shale Shells	1120
Shell Shale	1435
Shale Shells	1685
Lime Broken	1940
Sand	1970
Shale-Lime	2115
Lime-Shale	2225
Shale Lime	2515
Lime-Shale	2700
Shale-Lime	2930
Lime-Shale	3065
Shale & Lime	3195
Lime-Shale	3240
Lime	3350
Lime Shale	3455
Shale-Lime	3520
Lime	3680
Chert-Lime	3720
Chat-Lime	3750
Lime	3802
Total Depth	3802

*Copy Certified Correct*  
*R. S. Baker*

The undersigned, Shawver-Graham, Inc., hereby certifies that the above log is a true and correct log of the formation encountered in drilling the above noted well as reflected by the Daily Drilling Reports.

RECEIVED SHAWVER-GRAHAM, INC.  
 CONSERVATION COMMISSION

MAR 22 1951

BY: Wm. L. Graham  
 Sec'y-Treas.

STATE OF KANSAS )  
 COUNTY OF SEDGWICK ) SS

CONSERVATION DIVISION  
 Wichita, Kansas

Be it remembered that on this 27th day of September, 1948, before me the undersigned, a notary public, duly commissioned in and for the County and State aforesaid, came William L. Graham, Sec'y-Treas. of SHAWVER-GRAHAM INC., a Corporation of the State of Kansas, personally known to me to be such officer, and to be the same person who executed as such officer the foregoing instrument of writing in behalf of said Corporation, and he duly acknowledge the execution of the same for himself and for said Corporation.

IN WITNESS WHEREOF, I have hereunto set my hand and official seal on the day and year last above written.

My commission expires: July 3, 1950.

Faye I Wilson  
 Notary Public.

