

STATE OF KANSAS  
STATE CORPORATION COMMISSION

Form CP-4


Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission

WELL PLUGGING RECORD

P. O. Box 17027  
Wichita, Kansas 67217  
NORTH

Stafford County, Sec. 4 Twp. 22 Rge. (E) 13(W)

Location as "NE/CNW/SE/SW" or footage from lines SE NW NE  
Lease Owner Poor Boy Corporation  
Lease Name Gates Well No. 1  
Office Address Route 2, Ellinwood, Kansas 67526  
Character of Well (completed as Oil, Gas or Dry Hole) oil  
Date well completed \_\_\_\_\_ 19\_\_\_\_  
Application for plugging filed July 9 19 74  
Application for plugging approved \_\_\_\_\_ 19\_\_\_\_  
Plugging commenced July 10 19 74  
Plugging completed July 23 19 74  
Reason for abandonment of well or producing formation depleted



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well G. R. Biberstein  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3759 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
		0	285'	8 5/8"	285'	none
			3757'	5 1/2"	3757'	1776.70

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Sanded back to 3600' and dumped 5 sacks of cement.  
Allied Cementing Company plugged well pumping in 2 sacks of hulls, 10 sacks of gel and 100 sacks of cement.

RECEIVED  
STATE CORPORATION COMMISSION  
JUL 26 1974  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor PIPE PULLERS, INC.  
Address Box 486, Ellinwood, Kansas 67526

STATE OF KANSAS COUNTY OF BARTON, ss.  
Evelyn Roth (employee of owner) or (owner-or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Evelyn Roth  
Ellinwood, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 25th day of July, 19 74

George A. Meyer  
Notary Public.

My commission expires Feb. 10, 1975

ROCKET DRILLING COMPANY  
352 NORTH BROADWAY  
WICHITA 2, KANSAS

15.185-00002-0000

DERBY DRILLING COMPANY, ETAL.  
352 NORTH BROADWAY  
WICHITA 2, KANSAS

GATES #1  
SE NW NE; 4-22-13W  
STAFFORD COUNTY, KANSAS

ELEVATION: 1896 R.B.  
SPUDDED: DECEMBER 12, 1951  
ROTARY COMPLETED: DECEMBER 23, 1951  
CABLE TOOLS COMPLETED:  
ACID TREATMENT:  
CONTRACTOR: ROCKET DRILLING COMPANY

RECEIVED  
STATE CORPORATION COMMISSION  
JUL 10 1974  
CONSERVATION DIVISION  
Wichita, Kansas

CASING RECORD

285' 8-5/8" O. D. 2 1/4# SEAMLESS CASING CEMENTED W/200 SACKS CEMENT.  
3757' 5-1/2" O. D. 1 1/4# SEAMLESS CASING CEMENTED W/100 SACKS CEMENT.

DRILLERS LOG

SURFACE SOIL & CLAY	0 TO 245	SHALE & LIME	2495 TO 2650
SHALE	610	LIME & SHALE	2775
RED BED & SHALE	738	LIME	2875
ANHYDRITE	763	SHALE & LIME	2955
SHALE & SHELLS	1065	LIME	3173
SHALE & SALT	1505	LIME & SHALE	3268
LIME & SHALE	1735	SHALE	3352
SHALE & LIME	1830	LIME	3622
LIME	1986	LIME & SHALE	3667
SAND	2008	CHERT & SAND	3677
LIME	2085	CHERT	3710
LIME & SHALE	2495	SHALE	3756
		DOLOMITE	3759TD

STATE OF KANSAS) SS:  
SEDGWICK COUNTY)

I HEREBY CERTIFY THAT TO THE BEST OF MY KNOWLEDGE AND BELIEF,  
THE FOREGOING LOG IS TRUE AND CORRECT.

ROCKET DRILLING COMPANY

By \_\_\_\_\_

SUBSCRIBED AND SWORN TO BEFORE ME, A NOTARY PUBLIC, IN AND FOR  
THE STATE AND COUNTY AFORESAID THIS 27TH DAY OF DECEMBER, 1951.

My Commission Expires: 12-3-55

\_\_\_\_\_  
NOTARY PUBLIC