

WELL PLUGGING RECORD

OR

FORMATION PLUGGING RECORD

Strike out upper line when reporting plugging of formations.

STATE OF KANSAS STATE CORPORATION COMMISSION

Give All Information Completely Make Required Affidavit Mail or Deliver Report to: Conservation Division State Corporation Commission 800 Bitting Building Wichita, Kansas

Stafford County. Sec. 4 Twp. 22 Rge. (E) 13 (W)

Location as "NE 1/4 NW 1/4 SW 1/4" or footage from lines Cen. SE SE NW

Lease Owner Cities Service Oil Company et al.

Lease Name Mueller "B" Well No. 2

Office Address Bartlesville, Oklahoma

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed April 13, 19 50

Application for plugging filed April 13, 19 50

Application for plugging approved April 13, 19 50

Plugging commenced April 13, 19 50

Plugging completed April 13, 19 50

Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production ----- 19 -----

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well C. D. Stough

Producing formation Kansas City Depth to top 3391 Bottom 3608 Total Depth of Well 3608 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Table with 7 columns: Formation, Content, From, To, Size, Put In, Pulled Out. Row 1: Formation, Content, From, To, Size 8-5/8", Put In 335', Pulled Out None.

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from ----- feet to ----- feet for each plug set.

3608' to 335' heavy mud
335' to 285' wood plug, rock bridge and 15 sacks cement
285' to 35' heavy mud
35' to base of cellar - wood plug and 10 sacks cement

MAY 12 1951
5-13-50

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to R. C. Cooper Box 751 Great Bend, Kansas

STATE OF Kansas, COUNTY OF Barton, ss. V. M. Conover (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.


(Signature) V. M. Conover

Box 751, Great Bend, Kansas (Address)

SUBSCRIBED AND SWORN to before me this 12th day of May, 19 50

W. G. Smith Notary Public

My commission expires March 12, 1951.



WELL RECORD

(Partnership)

Company Cities Service Oil Co. et al. Well No. 2 Farm Mueller "B"
 Location 330' North and 330' West of Center Sec. 4 T. 22 R. 13W
 Elevation 1898 (1896 Gr.) County Stafford State Kansas
 Drlg. Comm. April 2, 1950 Contractor Holt-Louis Drilling Company
 Drlg. Comp. April 12, 1950 Acid None
 T. D. 3608' Initial Prod. Dry Hole - Plugged and Abandoned 4-12-50

CALLING RECORD:

8-5/8" @ 335' cen. 250 cc cement

FORMATION RECORD:

sand & clay	0-133
clay	180
sand	230
shale	265
sand & shale	300
red bed	600
red bed & shale	745
anhydrite	765
shale & shells	900
shells & shale	1495
shale & shells	1650
lime & shale	1680
lime	1725
lime & shale	2165
shale & shells	2530
lime & shale	3015
lime	3608 T. D.

Top Landing	3391'
Penetration	217'
Total Depth	3608'

Drill stem test 3509-15, recovered 10' mud in 30 mins.

Drill stem test 3525-35, recovered 15' mud in 30 mins.

SYFO:	500'	0°
	1000'	0°
	1500'	0°
	2000'	0°
	2500'	0°
	3000'	0°

MAY 13 1950

PLUGGING
 FILE SEC 4 T. 22 R. 13W
 BOOK PAGE 147 LINE 214