

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Bldg.
Wichita, Kansas 67202

Form CP-4
Rev. 12-15-80

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit

COUNTY Stafford SEC. 4 TWP. 22S RGE. 13W E/W
Location as in quarters or footage from lines:
NE NE NW

Locate Well
correctly on above
Section Platt.

Lease Owner A. Scott Ritchie
Lease Name Mueller A #1 Well No. _____
Office Address Suite 950 - 125 No. Market, Wichita, Ks. 67202
Character of Well (Completed as Oil, Gas or Dry Hole): _____
Date Well Completed _____
Application for plugging filed _____
Plugging commenced 5/6/81
Plugging completed 5/11/81
Reason for abandonment of well or producing formation _____

_____ Depleted
Was permission obtained from the Conservation Division or it's
Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Maurice Leslie
Producing formation _____ Depth to top _____ bottom T.D. 3373'
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
				8-5/8"	332'	None
				5 1/2"	3768'	3021'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Moved onto location. Made bottom hole plug back with sand to 3400'. Mixed and ran 5 sacks cement thru dump baler. Pulled 21" tension. Made shots at 3060 and 3000'. Worked pipe free and pulled 66 joints. Tallied pipe. Pulled 2 joints. Circulated 25 sacks gel thru 5 1/2" casing at 850. Pulled 15 joints. Circulated 125 sacks cement thru 5 1/2" casing at 400. Pulled 13 joints. Tore down. Tallied pipe. Plugging complete.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor KELSO CASING PULLING

STATE OF Kansas COUNTY OF Rice, ss.

~~XXXXXXXXXXXX~~ R. Darrell Kelso (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) [Signature]
Chase, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 13th day of May, 1981

My Commission expires: _____



[Signature] RECEIVED
STATE CORPORATION COMMISSION

MAY 14 1981 5-14-81
CONSERVATION DIVISION
Wichita, Kansas

WELL LOG

Mueller A-1
 NE NE NW 4-22-13
 Stafford County, Kansas

From	To		Elevation	1902	KB
0	200	Clay and Sand			
200	260	Shale, Shells, Sand			
260	332	Shale	Formation Tops		
332	766	Red Bed and Sand			
766	785	Anhydrite	Anhydrite	752	
785	1035	Red Bed and Shale	Topeka	2854	
1035	1150	Shale and Shells	Heebner	3227	
1150	2450	Lime and Shale	Douglas	3260	
2450	2720	Shale and Lime	Brown Lime	3350	
2720	2855	Lime	Lansing	3371	
2855	3040	Lime and Shale	Conglomerate	3600	
3040	3206	Lime	Viola	3645	
3206	3350	Shale and Lime	Simpson	3694	
3350	3685	Lime	Arbuckle	3745	
3685	3692	Lime and Chert	R T D	3770	
3692	3735	Shale and Lime			
3735	3770	Lime			
3770		Total Depth			

STATE OF KANSAS

COUNTY OF BARTON ss

R.K. Sweetman

, Partner of S & S Drilling Company, Being first duly sworn on oath says: That I have knowledge of the facts, statements and matters herein contained and the log of the above described well as filed and that the same are true and correct.


R.K. Sweetman

Subscribed and sworn before me this 28th day of December, 1964.

[Signature]

Notary Public

Barton County



Commission Expires April 24, 1967

RECEIVED
 STATE CORPORATION COMMISSION

MAR 26 1981

CONSERVATION DIVISION
 Wichita, Kansas