

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15.185.22 477.0000

LEASE NAME Chase Well Service

WELL NUMBER 1

4290 Ft. from S Section Line

2970 Ft. from E Section Line

SEC. 4 TWP. 22 RGE. 13 (E) or (W)

COUNTY Stafford

Date Well Completed 11/7/87

Plugging Commenced 11/7/87

Plugging Completed 11/7/87

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Trans Pacific Oil Corporation

ADDRESS 410 One Main Place

PHONE# (316) 262-3596 OPERATORS LICENSE NO. 09408

Character of Well D&A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on _____ (date)

by Richard Lacey (KCC District Agent's Name).

Is ACO-1 filed? yes If not, is well log attached? yes, Driller Log

Producing Formation _____ Depth to Top _____ Bottom T.D. 3900

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet each set.

PER ATTACHED

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Trans Pac Drilling, Inc.

STATE OF KANSAS License No. 05841

Address 410 One Main Place, Wichita, Ks. 67202

1-15-88

STATE OF Kansas COUNTY OF Sedgwick;

ss. CONSERVATION DIVISION
Wichita, Kansas

Gary Pugh

(Employee of Operator) or (Operator) of

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.


(Signature) Gary Pugh

(Address) Rt. 1 Seward, Ks. 67577

SUBSCRIBED AND SWORN TO before me this 6th day of January, 19 88

Sandra J. Follis
Notary Public

My Commission Expires: May 13, 1991



Trans Pacific Oil Corporation
410 One Main Place
Wichita, Kansas 67202

DRILLERS LOG

1 Chase Well Service
NE NE NW 4-22-13W
Stafford County,
Kansas

Spud Date: 10/31/87
Comp. Date: 11/7/87

0-345	Sand & Shale
345-625	Sand & Shale
625-1405	Red Beds
1405-1750	Shale & Lime
1750-1975	Shale
1975-2240	Lime & Shale
2240-2475	Lime & Shale
2475-2700	Shale
2700-2920	Shale & Lime
2920-3073	Lime & Shale
3073-3215	Shale
3215-3375	Lime & Shale
3375-3500	Lime & Shale
3500-3590	Shale
3590-3600	Lime & Shale
3600-3605	Lime
3605-3674	Lime & Shale
3674-3713	Chert
3713-3795	Lime & Shale
3795-3800	Lime
3800-3835	Lime & Shale
3835-3900	Lime

Surface Pipe : Set 336' of 8 5/8" surface pipe with 200 SX

This well was plugged as follows:

Bottom plug @ 3870 w/30 SXS
2nd plug @ 780' w/50 SX
3rd plug @ 360' w/40 SX
Top plug @ 40' w/10 SX to surface
15 SX Rat Hole
10 SX Mouse Hole
10 SX in Water Well

REGISTERED
STATE OF KANSAS
NOTARY PUBLIC

JAN 15 1988

CONSERVATION DIVISION
Wichita, Kansas

AFFIDAVIT

STATE OF KANSAS
COUNTY OF SEDGWICK ss

Alan D. Banta of lawful age does swear and state that the facts and statements herein are true and correct to the best of his knowledge.

Alan D. Banta
Alan D. Banta

Subscribed and sworn to before me this 6th day of January 1988

My Commission Expires:

May 13, 1991

Sondra J. Follis
Notary Public
Sondra J. Follis