


STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittling Building
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Flat

Stafford County, Sec. 3 Twp. 22 Rge. 13 (E) (W)
Location as "NE/CNW/SW" or footage from lines SE NW NW
Lease Owner Petroleum, Inc.
Lease Name Gates 'A' Well No. 4
Office Address 305 East Third, Wichita 2, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed June 30, 19 52
Application for plugging filed June 30, 19 52
Application for plugging approved June 30, 19 52
Plugging commenced June 30, 19 52
Plugging completed June 30, 19 52
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Mr. M. A. Rives
Producing formation Depth to top Bottom Total Depth of Well 3786 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

| FORMATION | CONTENT | FROM | TO | SIZE | PUT IN | PULLED OUT |
|-----------|---------|------|----|--------|--------|------------|
| | | | | 8 5/8" | 254' | None |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Mudded up to 250' and set wooden plug at 250'.
Cemented and displaced 20 sacks cement through
drill pipe onto plug at 250'. Mudded up to
35' and set second wooden plug. Placed 1/2 sack
hulls on top of plug at 35'. Filled hole to
bottom of well cellar, with 10 sacks cement.

CONSERVATION DIVISION
Wichita, Kansas

7-752

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Garvey Drilling Company
Address R. R. #2, Great Bend, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
W. W. Fisher (employee of owner) ~~owner~~ of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) W. W. Fisher
305 East Third, Wichita 2, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 3rd day of July 19 52
Charlotte Heidman
Notary Public.

My commission expires October 13, 1954.

PLUGGING
FILE SEC 3 T 22 R 13
BOOK PAGE 27 LINE 35

DRILLER'S LOG GATES 'A' NO. 4

Petroleum, Inc., Operator

Section 3, Twp. 22S, Rge. 13W

Garvey Drilling Company, Contractor

Location: SE NW NW

Drilling Commenced: June 20, 1952

County: Stafford County, Kansas

Drilling Completed: June 30, 1952

R.T.D.: 3786'

Casing Record: 8 5/8" @ 254' w/175' sax

Production: D & A

Figures below indicate bottom of formation:

253 Surface shale & Sand
 732 Red Bed
 758 Anhydrite
 1645 Shale & Shells
 2170 Lime & Shale
 2590 Shale & Shells
 3399 Lime & Shale
 3505 Lime
 3720 Cherty Viola
 3774 Lime & Shale
 3786 Lime

Tops:

Heebner: 3226 (-1335)
 Brown Lime: 3354 (-1463)
 Lansing: 3374 (-1483)
 Simpson: 3718 (-1827)
 Arbuckle: 3772 (-1881)

3786' R.T.D.

DST #1, 3773-76, open 20 mins., rec. 5' mud, 0# BHP.
 DST #2, 3774-81, open 1 hour, rec. 15' slightly oil cut mud, 0# BHP.
 DST #3, 3775-86, open 20 mins., rec. 8' mud, 35# BHP.

I hereby certify that this is a true and correct log of the above mentioned well.

PETROLEUM, INC.

By W.W. Fisher

State of Kansas :
 : SS:
 County of Sedgwick:

Subscribed to and sworn to before me, a Notary Public in said County and State, this 3rd day of July, 1952.

Charlotte Sherman
 RECEIVED Notary Public
 STATE CORPORATION COMMISSION

My commission expires: October 13, 1954. JUL - 7 1952

CONSERVATION DIVISION
 Wichita, Kansas

PLUGGING
 FILE SEC 3 T 22N 13W
 BOOK PAGE 27 LINE 35