

STATE OF KANSAS
STATE CORPORATION COMMISSION


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittling Building
Wichita, Kansas

Stafford County, Sec. 3 Twp. 22 Rge. 13 (E) (W)

Location as "NE/CNW%SW%" or footage from lines SW SE NW
Lease Owner Petroleum, Inc.
Lease Name Gates 'B' Well No. 4
Office Address 305 East Third, Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed January 7, 1953 19
Application for plugging filed January 7, 1953
Application for plugging approved January 7, 1953
Plugging commenced January 7, 1953
Plugging completed January 7, 1953
Reason for abandonment of well or producing formation Dry Hole

NORTH



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Mr. M. A. Rives
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3775 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	248'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Mudded up to 240' and set wooden plug at
240'. Cemented and displaced 20 sacks
cement through drill pipe onto plug at 240'.
Mudded up to 35' and set second wooden plug.
Filled hole to bottom of well cellar with
10 sacks cement.

RECEIVED
STATE CORP COMMISSION
JAN 17 1953

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Garvey Drilling Company
Address R. R. #2, Great Bend, Kansas

1-17-53

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
W. W. Fisher (employee of owner) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) W W Fisher
305 East Third, Wichita 2, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 16th day of January, 1953

Charlotte Heidman
Notary Public.

My commission expires October 13, 1954

PLUGGING
FILE SEC 3 T 22 1953
BOOK PAGE 72 LINE 6

DRILLER'S LOG GATES 'B' #4

Petroleum, Inc., Operator	Section 3, Twp. 22S., Rge. 13W
Garvey Drilling Company, Contractor	Location: SW SE NW
Drilling Commenced: December 26, 1952	County: Stafford County, Kansas
Drilling Completed: January 7, 1953	R.T.D.: 3774'
Casing Record: 8 5/8" @ 248' w/175 sax	Production: D & A

Figures below indicate bottom of formation:

150	Sand & Gravel	
238	Sand & Shale	
248	Blue Shale	<u>Tops:</u>
600	Red Rock & Shale	Heebner: 3225 (-1332)
700	Sand & Shale	Brown Lime: 3353 (-1460)
733	Red Bed & Shale	Lansing: 3371 (-1478)
760	Anhydrite	Arbuckle: 3755 (-1862)
1200	Shale & Shells	DST #1, 3494, 3547, open 45 mins., rec. 15'
1300	Salt & Shale	mud, 0# BHP.
1490	Shale & Shells	DST #2, 3668-3708, open 1 hr., rec. 30'
1715	Lime & Shale	mud, 0# BHP.
1820	Lime	DST #3, 3756-59, open 40 mins., rec. 8' mud,
2005	Lime & Shale	60# BHP.
2100	Lime	DST #4, 3757-64, open 30 mins., rec. 30'
3035	Lime & Shale	oil cut mud, 0# BHP.
3120	Lime	DST #5, 3758-3769, open 1 hr., rec. 570'
3370	Lime & Shale	gas, 90' heavily oil cut mud, 180#BHP.
3640	Lime	DST #6, 3759-3774, open 1 hr., rec. 70'
3652	Lime & Shale	oil cut mud, BHP 130#.
3708	Cherty Viola	
3750	Sand & Shale	
3756	Shale	
3774	Lime	
3774'	R.T.D.	

I hereby certify that this is a true and correct log of the above mentioned well.

PETROLEUM, INC.

PLUGGING
 FILE NO. 3 T 22 R 133
 BOOK PAGE 72 LINE 6

By W. F. FOLWELL
 STATE OF KANSAS

STATE OF KANSAS)
) SS:
 COUNTY OF SEDGWICK)

Sworn to and subscribed to before me, a Notary Public, in said County and State, this 12th day of January, 1953.

Charlotte Thomas
 Notary Public

My commission expires: October 13, 1954.