

WELL PLUGGING RECORD

Give All Information Completely
 Make Required Affidavit

COUNTY Stafford SEC. 3 TWP. 22 RGE. 13 E/W
 Location as in quarters or footage from lines:
 NE/SW/NW

Lease Owner Petroleum, Inc.
 Lease Name Gates "B" Well No. #3
 Office Address Box 1447 - Great Bend, Ks. 67530
 Character of Well (Completed as Oil, Gas or Dry Hole): Oil
 Date Well Completed _____
 Application for plugging filed _____
 Plugging commenced August 15, 1983
 Plugging completed August 23, 1983
 Reason for abandonment of well or producing formation Depleted
 Was permission obtained from the Conservation Division or it's Agent's before plugging was commenced? Yes

Locate Well
 correctly on above
 Section Platt.

Name of Conservation Agent who supervised plugging of this well J. H. Metz
 Producing formation _____ Depth to top _____ bottom _____ T.D. 3797'
 Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
				8 5/8"	244'	NONE
				4 1/2"	3796'	303.04

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Sanded to 3700' and dumped four (4) sacks cement.
 Pulled fourteen (14) joints 4 1/2" casing.
 Squeezed well with two hundred fifty (250) sacks 60/40 pozmix cement with 2% added gel and 3% calcium chloride. Shutin at 200 psi.


(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Rockhold Engineering, Inc.

STATE OF KANSAS COUNTY OF BARTON, ss.
James W. Rockhold (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) James W. Rockhold
 JAMES W. ROCKHOLD - Box 698 - Great Bend, Ks.
 (Address) 67530

SUBSCRIBED AND SWORN TO before me this 15th day of September, 1983



Margaret Prosser
 STATE CORPORATION COMMISSION
 Notary Public.
 SEP 2 1983
 CONSERVATION DIVISION
 Wichita, Kansas

My Commission expires:

15-185-10896-0000

Company- Patro, Inc.
Farm- Gates "B"

No. 3

SEC. 3 T. 22 R. 13W
CE/2 SW NW

Total Depth. 3796


Comm. 9-30-52

Comp. 10-11-52

Shot or Treated.

Contractor. Garvey Drlg. Co.

Issued. 12-13-52

County Stafford
KANSAS

Elevation. 1893

Production. Pmp. 59 B0 & NW

CASING:

8 5/8" 244' cem. w/175 sx
4 1/2" 3795' cem. w/110 sx

Figures indicate Bottom of Formations.

sand & clay	40
sand & shale	220
shale blue	244
shale blue & redbed	733
anhydrite	765
shale & shells	1175
salt & shale	1300
shale & shells	1650
lime & shale	3158
lime	3200
shale & shells	3350
lime	3635
viola	3689
shale	3743
lime	3793 RTD
lime	3796
Total Depth	

Tops:

Heebner	3222
Lansing	3369
Arbuckle	3743

DST: #1, 3431-37' open 1 hr.

rec. 55' mud, 820# BHP.

DST: #2, 3484-15' open 1 hr.

rec. 12' mud, 0# BHP

DST: #3, 3542-64' open 1 hr.

rec. 60' oil cut mud, 180'

gas 235# BHP

DST: #4, 3744-48' open 1/2

hr. rec. 7' mud 0# BHP.

DST: #5, 3745-53, open 1 hr.

rec. 840' free oil, 120'

gassy oil BHP 1290#.

RECEIVED
STATE COMMISSION
FEB 8 1983
UNCONVENTIONAL DIVISION
Wichita, Kansas