

STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD


Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Blitting Building  
Wichita, Kansas

OR

FORMATION PLUGGING RECORD

Strike out upper line  
when reporting plugging  
of formations.

NORTH



Locate well correctly on above  
Section Plot

Stafford County. Sec. 3 Twp. 22S Rge. 13 (E) W. (W)

Location as "NE $\frac{1}{4}$ NW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines SE/4 NE/4 SE/4

Lease Owner: Sterling Drilling Company

Lease Name: Kisner Well No. 1

Office Address: Sterling, Kansas

Character of Well (completed as Oil, Gas or Dry Hole): Dry Hole

Date well completed: August 14, 1947

Application for plugging filed: August 29, 1947

Application for plugging approved: August 29, 1947

Plugging commenced: August 29, 1947

Plugging completed: August 31, 1947

Reason for abandonment of well or producing formation: Dry Hole

If a producing well is abandoned, date of last production: 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well: Herb Kerr

Producing formation: Depth to top: Bottom: Total Depth of Well: 3728 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
				8-5/8"	295'	
				5 1/2"	3726'	2904'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Set bridge at 3330. Dumped 6 sacks cement. Set bridge at bottom of surface pipe. Dumped 15 sacks cement and 10 sacks at top.

10-10-47

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to: Sterling Drilling Company  
Address: Sterling, Kansas

STATE OF Kansas, COUNTY OF Rice, ss.

Rollin Mead (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Rollin Mead

Sterling, Kansas (Address)

SUBSCRIBED AND SWORN to before me this 10th day of October, 1947

F. A. Mueller  
Notary Public.

My commission expires 9-17-49

21-6858-RS 2-47-GM  
PLUGGING  
FILE SEC-3 Twp 22 R 13W  
BOOK PAGE 139 LINE 8

WELL LOG - - - - - KISNER #1

LOCATION - SE/4 NE/4 SE/4 Section 3-22S-13W, Stafford County, Kansas.

Owner - Sterling Drilling Company  
 Contractor - Sterling Drilling Company

Commenced - July 12, 1947  
 Completed - July 24, 1947 (With Rotary)

Total Depth - 3726' (-1841) with rotary

Casing Record

295' 8-5/8" Surface Pipe  
 Cemented with 225 Sacks Cement  
 3726' 5 1/2" Casing  
 Cemented with 125 Sacks Cement

LOG

0- 40 Surface Clay  
 40- 220 Sand  
 220- 720 Red Bed  
 720- 745 Lime  
 745-1000 Shale  
 1000-1445 Salt & Shale  
 1445-1520 Shale  
 1520-1675 Lime & Shale  
 1675-1990 Lime  
 1990-2310 Lime & Shale  
 2310-2360 Shale  
 2360-2490 Shale & Shells  
 2490-2720 Shale  
 2720-2950 Shale & Lime  
 2950-3200 Lime  
 3200-3325 Lime & Shale  
 3325-3530 Lime  
 3530-3623 Shale & Lime  
 3623-3665 Lime  
 3665-3694 Shale  
 3694-3699 Sand  
 3699-3720 Shale  
 3720-3728 Lime


Formation Tops

Brown Lime	3324	-1439
Lansing	3348	-1463
Cong. (Cherty)	3616	-1731
Viola (Cherty)	3621	-1736
Simpson	3664	-1779
Arbuckle	3723 1/2	-1838 1/2

Production

None - - - - - Dry

Total Depth - 3728'



PLUGGING  
 FILE SEC-3 T 22 R 13W  
 BOOK PAGE 139 NO 8