


WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Biting Building  
Wichita, Kansas

Stafford County. Sec. 3 Twp. 22 Rge. 13 (E) (W)  
Location as "NE/CNW%SW%" or footage from lines NW SE SW  
Lease Owner Petroleum, Inc.  
Lease Name Wood-Nicholson Well No. 1  
Office Address 305 East Third, Wichita, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed October 23, 19 53  
Application for plugging filed October 23, 19 53  
Application for plugging approved October 23, 19 53  
Plugging commenced October 23, 19 53  
Plugging completed October 23, 19 53  
Reason for abandonment of well or producing formation Dry Hole



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Mr. M.A. Rives  
Producing formation Depth to top Bottom Total Depth of Well 3857 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	249'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Mudded up to 240' and set wooden plug at 240'. Placed 1/4 sack hulls on top of plug at 240'. Cemented and displaced 20 sacks cement through pipe onto plug and hulls at 240'. Mudded up to 40' and set second wooden plug at 40'. Placed 1/4 sack hulls on top of plug at 40'. Filled hole to bottom of well cellar with 10 sacks cement.

10-27-53

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Garvey Drilling Company  
Address R.R. #2, Great Bend, Kansas


STATE OF KANSAS, COUNTY OF SEDGWICK, ss.  
W.W. Fisher (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) W.W. Fisher  
305 East Third, Wichita, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 26th day of October, 19 53

My commission expires October 13, 1954.

Charlotte Sherman Notary Public.



DRILLER'S LOG WOOD - NICHOLSON #1

Petroleum, Inc., Operator  
 Garvey Drilling Company, Contractor

Section 3, Twp. 22S, Rge. 13W  
 Location: NW SE SW  
 County: Stafford County, Kansas  
 Production: D & A  
 R.T.D.: 3857'

Drilling Commenced: October 10, 1953  
 Drilling Completed: October 21, 1953

Casing Record: 8.5/8" @ 249' w/200 sax

Figures below indicate bottom of formation:

100 Fine Surface Sand  
 240 Coarse Sand & Shale  
 249 Blue Shale  
 705 Red Bed & Sand  
 740 Red Bed  
 767 Anhydrite  
 1550 Shale & Shells  
 3393 Lime & Shale  
 3666 Lime  
 3729 Chert  
 3779 Shale  
 3857 Lime  
 3857 R.T.D.

TOPS  
 Heebner: 3239 (-1348)  
 Brown Line: 3365 (-1474)  
 Lansing: 3384 (-1493)  
 Simpson: 3729 (-1838)  
 Arbuckle: 3778 (-1887)

I hereby certify that this is a true and correct log of the above mentioned well.

PETROLEUM, INC.

By W.W. Fisher

STATE OF KANSAS )  
 ) SS:  
 COUNTY OF SEDGWICK)

Subscribed to and sworn to before me, a Notary Public, in said County and State, this 26th day of October, 1953.

Charlotte Thaidman  
 Notary Public

My commission expires: October 13, 1954.

**PLUGGING**  
 FILE SEC 3 T 22 R 134  
 BOOK PAGE 127 LINE 23