

State of Kansas



FORM - CP-2
Rev. 9-8-64

15-009-19303-0000

JOHN ANDERSON, Jr. Governor
WILLIAM L. MITCHELL Chairman
ALVIN P. GRAUERHOLZ Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
ROBT. C. LONDERHOLM Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

MAR 8 1965
03-08-85
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Adminstrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. Harold Yowell of Herman Geo. Kaiser has this
Oil Producer
date requested permission to plug the following described well:

Mr. Herman Geo. Kaiser guarantees payment of the plugging fee.

Operator's full Name: Herman Geo. Kaiser, Oil Producer

Complete Address: 909 Palace Bldg., Tulsa, Oklahoma 74103

Lease Name: Woydziak "B" Well No. # 1

Location: SW SW NE Sec. 1 Twp. 16 Rge. 12 (E)(W)X

County Barton Total Depth 3325 Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Russell Hoberecht was instructed to plug the well as follows:

8 5/8" 289' Cwc.

Sanded hole back to 2860' & dumped 5 sax cement with

dump bailer. Pulled pipe. Mudded hole to 270'; set rock

bridge; displaced 25 sax cement. Mud to 40'; set rock bridge;

displaced 10 sax cement, cementing to base of cellar.

Very truly yours,

Don Truman
Conservation Division Agent