



JOHN ANDERSON, Jr. Governor
 RICHARD C. BYRD Chairman
 ALVIN F. GRAUERHOLZ Commissioner
 HARRY G. WILES Commissioner
 RAYMOND B. HARVEY Secretary
 CHARLES C. McCARTER Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
 500 Insurance Bldg. 212 N. Market
 WICHITA, KANSAS

VERBAL PERMIT FORM
 (To Be Filed By Plugging Agent)

RECEIVED
 STATE CORPORATION COMMISSION

NOV 9 1962

CONSERVATION DIVISION
 Wichita, Kansas

11-9-62

J. P. Roberts
 Assistant Director
 500 Insurance Building
 212 North Market
 Wichita 2, Kansas

Dear Sir:

Mr. Bill Neal of Leben Drilling, Inc. has this

date requested permission to plug the following described well:

Mr. Herman George Kaise guarantees payment of the plugging fee.

Operator's full Name: Kaiser-Francis Oil Producers

Complete Address: 909 Palace Bldg., Tulsa 3, Oklahoma

Lease Name: Schauf Well No. # 1

Location: NE NE SE Sec. 2 Twp. 16 Rge. 12 (E) (W)

County Barton Total Depth 3390 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Bill Neal was instructed to plug the well as follows:

8 5/8" 307' Gwc.

Fill hole with heavy mud to 300', set plug with 1/4
sax hulls, plug, & displace 25 sax cement thru drill
pipe. Mud to 35', 1/2 sax hulls, plug, & displace 10
sax cement, cementing to base of cellar.

Very truly yours,

Don't Swan
 Conservation Division Agent