



JOHN ANDERSON, Jr. Governor
 RICHARD C. BYRD Chairman
 ALVIN F. GRAUERHOLZ Commissioner
 HARRY G. WILES Commissioner
 RAYMOND B. HARVEY Secretary
 CHARLES C. McCARTER Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
 500 Insurance Bldg. 212 N. Market
 WICHITA, KANSAS

VERBAL PERMIT FORM
 (To Be Filed By Plugging Agent)

15-185-11334-000

RECEIVED
STATE CORPORATION COMMISSION

DEC 2 1963

12-2-63

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
 Assistant Director
 500 Insurance Building
 212 North Market
 Wichita 2, Kansas

Dear Sir:

Mr. Wayne Dobbs of Vaughn Drilling Co. has this

date requested permission to plug the following described well:

Mr. Dobbs guarantees payment of the plugging fee.

Operator's full Name: Abercrombie Drilling Inc.

Complete Address: 801 Union Center, Wichita, Kansas

Lease Name: Smith "A" Well No. # 1

Location: NW NW NW Sec. 30 Twp. 23 Rge. 13 (E) (W) W

County Stafford Total Depth 3830 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Dobbs was instructed to plug the well as follows:

223' of 8 5/8" surface pipe, cemented with 185 sacks.
Fill hole with drilling mud to 250', 1st cementing plug,
1/4 sack hulls, cement with 25 sacks. Fill hole with drill-
ing mud to 40', 2nd cementing plug, 1/4 sack hulls, cement
with 10 sacks to base cellar. Bridge and cement rat hole
with 2 sacks.

Very truly yours,

Archie Elving
 Conservation Division Agent