



15-185-30197-0000

WM. H. AVERY Governor  
WILLIAM L. MITCHELL Chairman  
JOHN C. WOELK Commissioner  
HARRY G. WILES Commissioner  
RAYMOND B. HARVEY Secretary  
E. EDWARD JOHNSON Gen. Counsel

# State Corporation Commission

## CONSERVATION DIVISION

(Oil, Gas and Water)  
500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

### VERBAL PERMIT FORM (To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION  
11-24-65  
NOV 24 1965

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita 2, Kansas

CONSERVATION DIVISION  
Wichita, Kansas

Dear Sir:

Mr. Howard Roberts of Strata Drilling, Inc. has this

date requested permission to plug the following described well:

Mr. Roberts guarantees payment of the plugging fee.

Operator's full Name: Kirby Petroleum Company

Complete Address: 402 First National Bank Bldg., Pawhuska, Okla.

Lease Name: Gates Well No. # A-3

Location: NW NW NE Sec. 4 Twp. 22 Rge. 13(E)(W) W

County Stafford Total Depth 3758' Oil Well

Gas Well  Input Well  SWD Well  D & A X Lost Hole

Mr. Roberts was instructed to plug the well as follows:

325' of 8 5/8" surface pipe, cement circulated with 285 sacks.

Fill hole with drilling mud to 260', 1st cementing plug, bridge

with hulls, and cement with hulls, and cement with 25 sacks c Fill

hole with drilling mud to 40', 2nd cementing plug, bridge with hulls,

and cement with 10 sacks to base of the cellar, Bridge and cement rat

hole with 2 sacks.

Very truly yours,

Archie Claring  
Conservation Division Agent