



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market

WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
MAY 10 1971
CONSERVATION DIVISION
Wichita, Kansas

5-10-71

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Radke of Garvey Drlg. Co. has this date requested permission to plug the following described well:

Mr. Radke guarantees payment of the plugging fee.

Operator's full Name: United States Hydrocarbon Co.

Complete Address: Box 11027 Wichita, Ks

Lease Name: Chase Well Service Well No. 2

Location: 990' EWL & 810' SNL Sec. 4 Twp. 22s Rge. 13 (E)(W) W

County: Stafford Total Depth 3800 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Radke was instructed to plug the well as follows:

290 ft of 8 5/8 surface pipe cemented with 275 sacks. Pumped
40 sacks cement to 600 ft. Fill hole to 280 ft, pump 25
sacks cement. Mud to 40 ft, 1/2 sack hulls, plug, 10 sacks
cement to surface. 3 sacks cement in rat hole, 3 sacks
cement in mouse hole.

Pumped by Globe Cementing Co. Great Bend, Ks
Very truly yours,

L. Russell Biberstein
Conservation Division Agent