

6 070254

API NUMBER 15-009-23, 778-00-00

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION E 1/2 - NW - SW, SEC. 2, T 16 S, R 12 @ 1E
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

1980 feet from S section line
4290 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6330
Operator: CARL BOXBERGER
Name & Address: P.O. BOX 474
GREAT BEND, KANS.
67530

Lease Name SCHAUF Well # 1
County BARTON 110.44
Well Total Depth 3398 feet
Conductor Pipe: Size 0 feet
Surface Casing: Size 8 5/8 feet 423 ✓

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated TAG # 1730

Plugging Contractor BOGER BROS. DRUG CO. License Number 9421

Address HOLSDINGTON, KANSAS

Company to plug at: Hour: 9:00 AM Day: 18th Month: NOV. Year: 19 84

Plugging proposal received from DALE SMITH

(company name) BOGER BROS. DRUG CO. (phone) 316-793-6032

were: 8 5/8" 423' SQ. CUC #/225^{SK 60} / 40 Pozmix GEL - CH. CL. - BY HALLIBURTON
ORDER 180^{SK 50} / 50 Pozmix GEL - CH. CL. - 1^{SK 70} CELE AND 8 5/8" PUG.

SPOT WITH DRILL STEM - TURN HOLE OVER - HEAVY MUD BETWEEN ALL PLUGS
(CONGLOMERATE WELL), NO CIRCULATION PROBLEMS, ELV. 1887' - ANH. 483.
MUD VISCOSITY 48 - weight - 9.6^{lb}

Plugging Proposal Received by Marion Schmidt
BOK (TECHNICIAN)

Plugging Operations attended by Agent AM All _____ Part _____ None X

Operations Completed: Hour: 10:30 Day: 18th Month: NOV Year: 19 84

ACTUAL PLUGGING REPORT ORDERED 180^{SK 50} / 50 Pozmix GEL - CH. CL. - 1^{SK 70} CELE + 8 5/8" PUG.

SPOTTED WITH DRILL STEM - TURNED HOLE OVER - HEAVY MUD BETWEEN ALL PLUGS.
1ST PLUG @ 800 FT #/30^{SK} CNT - 2ND PLUG @ 570 FT #/80^{SK} CNT + 1ST CELE.
3RD PLUG @ 240 FT #/50^{SK} CNT, 4TH PLUG SOLID BRIDGE HULLS - PLUG @ 40 FT #/60
#/10^{SK} CNT, - 10^{SK} IN RAT HOLE - CEMENTED BY RECEIVED
(HALLIBURTON CNT) CONSERVATION COMMISSION

Remarks: _____
(If additional description is necessary, use BACK of this form.)
NOV 20 1984
17-26-84
CONSERVATION DIVISION
Wichita, Kansas

INVOICED

DATE 11-28-84

INV. NO. 4959 17-18

JAN 14 1985

Signed Marion Schmidt
(BOK) (TECHNICIAN) 11-21-84
17

CARD MUST BE TYPED

NOTICE OF INTENTION TO DRILL

CARD MUST BE SIGNED

Starting Date: November 5, 1984

API Number 15-009-23,778-00-00

OPERATOR: License # 6330
Name: Carl Boxberger
Address: P.O. Box 474
City/State/Zip: Great Bend, KS 67530
Contact Person: Keith Lumpkins
Phone: 316-793-6032

E/2 NW SW Sec 2 Twp 16S S, Rge 12 W
1980 Ft North from Southeast Corner of Section
4290 Ft West from Southeast Corner of Section
(Note: Locate well on Section Plat on reverse slide)
660

CONTRACTOR: License # 9421
Name: Boger Bros. Drilling Co.
City/State: Hoisington, KS

Nearest lease or unit boundary line ... feet.
County: Barton
Lease Name: Schauf Well# 1
Domestic well within 330 feet: [] yes [X] no
Municipal well within one mile: [] yes [X] no

Well Drilled For: Well Class: Type Equipment:
[] Oil [] Swd [] Infield [] Mud Rotary
[] Gas [] Inj [X] Pool Ext. [] Air Rotary
[] OWWO [] Expl [] Wildcat [] Cable

Depth to Bottom of fresh water ... 100 feet
Lowest usable water formation ... Dakota
Depth to Bottom of usable water ... 350 feet
Surface pipe by Alternate: 1 [X] 2 [] 400
Surface pipe to be set ... feet
Conductor pipe if any required ... 0 feet
Ground surface elevation ... 1880 feet MSI.
This Authorization Expires ... 5-2-85
Approved By ... 11-1-84

Operator:
Well Name:
Comp Date:
Projected Total Depth: 3475 feet
Projected Formation at TD: Arbuckle
Projected Producing Formations: Lans/Kc-Arb

Authority that we will comply with K.S.A. 55-101, et seq., plus eventually plugging hole to K.C.C. specifications. Kansas, All #2, 250' surf

Signature of Operator or Agent: Carl Boxberger Title: Owner

RECEIVED STATE CORPORATION COMMISSION

MAILED Form C-1 4/84

NOV 26 1984

NOV 13 1984

