

4-060484

12-21

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API number: 15-009-22,963-00-00

SE SE NW /4 SEC. 02, 16 S, 12 W
3245 feet from S section line
2790 feet from E section line

Operator license# 31142 Lease LaVerne well # 2-2

Operator: Petroleum Property Services, Inc. County Barton 108.42

Address: 155 N. Market Well total depth 3336 feet
Suite #1010 Conductor Pipe: 0 inch @ 0 feet
Wichita, Kansas 67202-1824 Surface pipe 8 5/8 Inch @ 485 feet

Aband. oil well X, Gas well , Input well , SWD , D & A

Plugging contractor: Kelso Casing Pullers, Inc. License# 6050

Address: P.O. Box 347 - Chase, Kansas 67524

Company to plug at: Hour: 9:30A.M. Day: 21 Month: December Year: 93

Plugging proposal received from: Mike Kelso

Company: Kelso Casing Pullers, Inc. Phone: 316-938-2943

Were: Order 185 sxs. 60/40 posmix - 10% gel and 200# hulls.
Plug while pulling casing.

RECEIVED
STATE CORPORATION COMMISSION

DEC 20 1993

12-29-93
CONSERVATION DIVISION
WICHITA, KANSAS

Plugging Proposal Received by: Herb Deines
Plugging operations attended by agent? All[X], Part[], None[]

Completed: Hour: 1:00P.M., Day: 21, Month: December, Year: 93

Actual plugging report: 8 5/8" to 485' w/250 sxs. 4 1/2" to 3333'
with 150 sxs. Sand to 3280' and spot 4 sxs. cement with dump bailer.
Shot casing at 2133' and pulled to 1600'. Mix and pump 35 sxs. cement
with 100# hulls and displace to 1450'. Pulled to 800' and mixed 75 sxs.
cement with 100# hulls. Pulled casing to 350' and circulated cement to
surface with 45 sxs. Pulled casing and topped off with 10 sxs.

Remarks: Allied Cementing.
Condition of casing(in hole): GOOD X BAD Anhy. plug: YES X NO
Bottom plug(in place): YES X, CALC , NO Dakota plug: YES X, NO
Plugged through TUBING , CASING X. Elevation: 1873 GL

I did X did not observe the plugging. Herb Deines

INVOICED
DATE 12-30-93
INV. NO. 39616

OH (agent)