

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-009,22,924-00-00

C-1/2 NE - SW, Sec. 2, T 16 S, R 12 W/2

330 feet from N/S section line
feet from W/E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5399

Lease Name SCHAEFF Well # 1-A

Operator: AMERICAN ENERGIES
Name & Address 575 1/2 FINANCIAL CTR.
WICHITA, KANS.

County BARTON

Well Total Depth 3370 feet

Conductor Pipe: Size 0 feet 0

Surface Casing: Size 8 5/8 feet 560

Abandoned Oil Well Gas Well Input Well SWD Well D&A X

Other well as hereinafter indicated

Plugging Contractor SUN OIL WELL CEMENTING License Number

Address BOX 69 HAYS, KANS. 67601

Company to plug at: Hour: 7:00 AM Day: Oct Month: 29 Year: 1982

VERBAL PLUGGING ORDERS GIVEN TO BILL ROACH.

(company name) J.W. DRILLING CO. (phone) 216-263-3705

were: 8 5/8" 560 FE. SP. CUL. 1/300 ST COMMON - 2% GEL - 3% CA-CL.

ORDER 180 ST 50/50 FORMIX 4% GEL - 3% CA-CL. AND 8 5/8" PLUG.

SPOT WITH DRILL STEM - WITH HEAVY MUD BETWEEN ALL PLUGS.

1st PLUG @ 3350 FE 1/20 ST CMT. -> 2nd PLUG @ 750 FE 1/100 ST CMT.

3rd PLUG @ 240 FE 1/40 ST CMT. 4th PLUG SOLID BRIDGE HULL'S - PLUG @ 40 FE 1/10 ST

10 ST IN RAT HOLE (CIRCULATE) Signed [Signature] (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: 3:45 PM Day: 29 Month: OCT Year: 1982

ACTUAL PLUGGING REPORT 8 5/8" - 560 FE CUL SP. 1/300 ST BY SUN CMT.

ORDERED 180 ST 50/50 FORMIX 4% GEL - 3% CA-CL. AND 8 5/8" PLUG.

SPOTTED WITH DRILL STEM - WITH HEAVY MUD BETWEEN ALL PLUGS.

1st PLUG @ 3350 1/20 ST CMT. 2nd PLUG @ 750 FE 1/100 ST CMT.

3rd PLUG @ 240 FE 1/40 ST CMT. 4th PLUG SOLID BRIDGE HULL'S - PLUG @ 40 FE 1/10 ST

10 ST IN RAT HOLE. (CIRCULATE) (CEMENTED BY SUN CMT.)

Remarks:

RECEIVED STATE CORPORATION COMMISSION

NOV 08 1982

CONSERVATION DIVISION Wichita, Kansas

11-8-82

I hereby certify that the above plugging instructions were given as herein stated and that I (did / did not) observe this plugging.

INVOICED
DATE 12-6-82
INV. NO. 1752-W

Signed [Signature] (TECHNICIAN)

1000000000000

1000000000000

1000000000000

1000000000000

1000000000000

1000000000000

1000000000000

1000000000000

1000000000000

1000000000000

1000000000000

1000000000000

1000000000000

1000000000000

1000000000000

1000000000000

1000000000000

1000000000000

1000000000000

1000000000000

1000000000000

1000000000000