

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

062342

API NUMBER 15-009-03238-0000

NE, SEC. 2, T 16 S, R 12 W/E

2970 feet from S section line

330 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5151

Lease Name LaVerne Weber # 1

Operator: Gear Petroleum Co. Inc.

County Barton 109.00

Name & Address 125 N. Market # 1075

Well Total Depth 3354 feet

Wichita, Ks. 67202

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 269

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D&A

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Gear Petroleum Co. Inc. License Number 5151

Address 125 N. Market Wichita, Ks. 67202

Company to plug at: Hour: 1:30PM Day: 6 Month: Feb. Year: 19 91

Plugging proposal received from Bill Hammack

(company name) Gear Pet. Co. Inc. (phone) 316-483-4828

were: Order 350 sks 60/40 poz 8% gel 5 sks hulls.

2-13-91

FEB 13 1991

Shot three holes at 850

Plugging Proposal Received by Gilbert G. Scheck  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 4:30PM Day: 6 Month: Feb. Year: 19 91

ACTUAL PLUGGING REPORT 8 5/8 set at 269 w/160 sks. 5 1/2 set at 3343 w/79 sks.

Top perf at 2900. Plugged bottom w/50 sks cement to 2900. ran tubing to 2850. Spotted 50 sks cement. Pulled tubing to 1100 and circ cement to surf. Pulled all tubing and hooked onto 5 1/2 and sq to 200 psi used 195 sks cement. Pumped in 8 5/8 55 sks w/350 psi.

Remarks: Allied. Holes in pipe.

(If additional description is necessary, use BACK of this form.)

INVOICED

(old) did not observe this plugging.

DATE 2-26-91

Signed

(TECHNICIAN)  
Gilbert G. Scheck

INV. NO. 30898